

# ENC28J60 Data Sheet

Stand-Alone Ethernet Controller with SPI<sup>TM</sup> Interface

© 2004 Microchip Technology Inc.

#### Note the following details of the code protection feature on Microchip devices:

- Microchip products meet the specification contained in their particular Microchip Data Sheet.
- Microchip believes that its family of products is one of the most secure families of its kind on the market today, when used in the intended manner and under normal conditions.
- There are dishonest and possibly illegal methods used to breach the code protection feature. All of these methods, to our knowledge, require using the Microchip products in a manner outside the operating specifications contained in Microchip's Data Sheets. Most likely, the person doing so is engaged in theft of intellectual property.
- Microchip is willing to work with the customer who is concerned about the integrity of their code.
- Neither Microchip nor any other semiconductor manufacturer can guarantee the security of their code. Code protection does not mean that we are guaranteeing the product as "unbreakable."

Code protection is constantly evolving. We at Microchip are committed to continuously improving the code protection features of our products. Attempts to break Microchip's code protection feature may be a violation of the Digital Millennium Copyright Act. If such acts allow unauthorized access to your software or other copyrighted work, you may have a right to sue for relief under that Act.

Information contained in this publication regarding device applications and the like is provided only for your convenience and may be superseded by updates. It is your responsibility to ensure that your application meets with your specifications. MICROCHIP MAKES NO REPRESENTATIONS OR WAR-RANTIES OF ANY KIND WHETHER EXPRESS OR IMPLIED, WRITTEN OR ORAL, STATUTORY OR OTHERWISE, RELATED TO THE INFORMATION, INCLUDING BUT NOT LIMITED TO ITS CONDITION, QUALITY, PERFORMANCE, MERCHANTABILITY OR FITNESS FOR PURPOSE. Microchip disclaims all liability arising from this information and its use. Use of Microchip's products as critical components in life support systems is not authorized except with express written approval by Microchip. No licenses are conveyed, implicitly or otherwise, under any Microchip intellectual property rights.

#### Trademarks

The Microchip name and logo, the Microchip logo, Accuron, dsPIC, KEELOQ, microID, MPLAB, PIC, PICmicro, PICSTART, PRO MATE, PowerSmart, rfPIC, and SmartShunt are registered trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.


AmpLab, FilterLab, Migratable Memory, MXDEV, MXLAB, PICMASTER, SEEVAL, SmartSensor and The Embedded Control Solutions Company are registered trademarks of Microchip Technology Incorporated in the U.S.A.

Analog-for-the-Digital Age, Application Maestro, dsPICDEM, dsPICDEM.net, dsPICworks, ECAN, ECONOMONITOR, FanSense, FlexROM, fuzzyLAB, In-Circuit Serial Programming, ICSP, ICEPIC, MPASM, MPLIB, MPLINK, MPSIM, PICkit, PICDEM, PICDEM.net, PICLAB, PICtail, PowerCal, PowerInfo, PowerMate, PowerTool, rfLAB, rfPICDEM, Select Mode, Smart Serial, SmartTel and Total Endurance are trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

 $\ensuremath{\mathsf{SQTP}}$  is a service mark of Microchip Technology Incorporated in the U.S.A.

All other trademarks mentioned herein are property of their respective companies.

© 2004, Microchip Technology Incorporated, Printed in the U.S.A., All Rights Reserved.



### QUALITY MANAGEMENT SYSTEM CERTIFIED BY DNV ISO/TS 16949:2002

Microchip received ISO/TS-16949:2002 quality system certification for its worldwide headquarters, design and wafer fabrication facilities in Chandler and Tempe, Arizona and Mountain View, California in October 2003. The Company's quality system processes and procedures are for its PICmicro® 8-bit MCUs, KEEL00® code hopping devices, Serial EEPROMs, microperipherals, nonvolatile memory and analog products. In addition, Microchip's quality system for the design and manufacture of development systems is ISO 9001:2000 certified.



**ENC28J60** 

### Stand-Alone Ethernet Controller with SPI<sup>TM</sup> Interface

#### **Ethernet Controller Features**

- IEEE 802.3 compatible Ethernet controller
- Integrated MAC and 10BASE-T PHY
- · Receiver and collision squelch circuit
- Supports one 10BASE-T port with automatic polarity detection and correction
- Supports Full and Half-Duplex modes
- Programmable automatic retransmit on collision
- Programmable padding and CRC generation
- Programmable automatic rejection of erroneous packets
- SPI™ Interface with speeds up to 10 Mb/s

#### Buffer

- 8-Kbyte transmit/receive packet dual port SRAM
- Configurable transmit/receive buffer size
- Hardware-managed circular receive FIFO
- Byte-wide random and sequential access with auto-increment
- Internal DMA for fast data movement
- Hardware assisted IP checksum calculation

#### Medium Access Controller (MAC) Features

- Supports Unicast, Multicast and Broadcast packets
- Programmable receive packet filtering and wake-up host on logical AND or OR of the following:
  - Unicast destination address
  - Multicast address
  - Broadcast address
  - Magic Packet™
  - Group destination addresses as defined by 64-bit hash table
  - Programmable pattern matching of up to 64 bytes at user-defined offset
- Loopback mode


#### Physical Layer (PHY) Features

- Wave shaping output filter
- Loopback mode

#### Operational

- Two programmable LED outputs for LINK, TX, RX, collision and full/half-duplex status
- · Seven interrupt sources with two interrupt pins
- 25 MHz clock
- · Clock out pin with programmable prescaler
- Operating voltage range of 3.14V to 3.45V
- TTL level inputs
- Temperature range: -40°C to +85°C Industrial, 0°C to +70°C Commercial (SSOP only)
- 28-pin SPDIP, SSOP, SOIC, QFN packages

#### Package Types



#### **Table of Contents**

1.0	Overview
2.0	External Connections
3.0	Memory Organization
4.0	Serial Peripheral Interface (SPI)
5.0	Ethernet Overview
6.0	Initialization
7.0	Transmitting and Receiving Packets
8.0	Receive Filters
9.0	Duplex Mode Configuration and Negotiation
10.0	Flow Control
11.0	Reset
12.0	Interrupts
13.0	Direct Memory Access Controller
14.0	Power-Down
15.0	Built-in Self-Test Controller
16.0	Electrical Characteristics
17.0	Packaging Information
Index	95
On-L	ine Support
	ms Information and Upgrade Hot Line
Read	er Response
Produ	uct Identification System

### TO OUR VALUED CUSTOMERS

It is our intention to provide our valued customers with the best documentation possible to ensure successful use of your Microchip products. To this end, we will continue to improve our publications to better suit your needs. Our publications will be refined and enhanced as new volumes and updates are introduced.

If you have any questions or comments regarding this publication, please contact the Marketing Communications Department via E-mail at **docerrors@microchip.com** or fax the **Reader Response Form** in the back of this data sheet to (480) 792-4150. We welcome your feedback.

#### Most Current Data Sheet

To obtain the most up-to-date version of this data sheet, please register at our Worldwide Web site at:

http://www.microchip.com

You can determine the version of a data sheet by examining its literature number found on the bottom outside corner of any page. The last character of the literature number is the version number, (e.g., DS30000A is version A of document DS30000).

#### Errata

An errata sheet, describing minor operational differences from the data sheet and recommended workarounds, may exist for current devices. As device/documentation issues become known to us, we will publish an errata sheet. The errata will specify the revision of silicon and revision of document to which it applies.

To determine if an errata sheet exists for a particular device, please check with one of the following:

• Microchip's Worldwide Web site; http://www.microchip.com

Your local Microchip sales office (see last page)

When contacting a sales office, please specify which device, revision of silicon and data sheet (include literature number) you are using.

#### **Customer Notification System**

Register on our web site at www.microchip.com to receive the most current information on all of our products.

### 1.0 OVERVIEW

The ENC28J60 is a stand-alone Ethernet controller with an industry standard Serial Peripheral Interface (SPI<sup>™</sup>). It is designed to serve as an Ethernet network interface for any controller equipped with SPI.


The ENC28J60 meets all of the IEEE 802.3 specifications. It incorporates a number of packet filtering schemes to limit incoming packets. It also provides an internal DMA module for fast data throughput and hardware assisted IP checksum calculations. Communication with the host controller is implemented via two interrupt pins and the SPI, with data rates of up to 10 Mb/s. Two dedicated pins are used for LED link and network activity indication.

A simple block diagram of the ENC28J60 is shown in Figure 1-1. A typical application circuit using the device is shown in Figure 1-2. With the ENC28J60, two pulse transformers and a few passive components are all that is required to connect a microcontroller to a 10 Mbps Ethernet network.

The ENC28J60 consists of seven major functional blocks:


- 1. An SPI interface that serves as a communication channel between the host controller and the ENC28J60.
- 2. Control Registers which are used to control and monitor the ENC28J60.
- 3. A dual port RAM buffer for received and transmitted data packets.
- 4. An arbiter to control the access to the RAM buffer when requests are made from DMA, transmit and receive blocks.
- 5. The bus interface that interprets data and commands received via the SPI interface.
- 6. The MAC (Medium Access Control) module that implements IEEE 802.3 compliant MAC logic.
- 7. The PHY (Physical Layer) module that encodes and decodes the analog data that is present on the twisted pair interface.

The device also contains other support blocks, such as the oscillator, on-chip voltage regulator, level translators to provide 5V tolerant I/Os and system control logic.



#### FIGURE 1-1: ENC28J60 BLOCK DIAGRAM





#### TABLE 1-1: PINOUT I/O DESCRIPTIONS

	Pin Nur	nber	Dia	Deffer				
Pin Name	SPDIP, SOIC, SSOP		Pin Type	Buffer Type	Description			
VCAP	1	25	Р	—	2.5V output from internal regulator. A 10 $\mu F$ capacitor to VSSTX must be placed on this pin.			
Vss	2	26	Р	—	Ground reference.			
CLKOUT	3	27	0	—	Programmable clock output pin. <sup>(1)</sup>			
INT	4	28	0	_	INT interrupt output pin. <sup>(2)</sup>			
WOL	5	1	0	_	Wake-up on LAN interrupt out pin. <sup>(2)</sup>			
SO	6	2	0	—	Data out pin for SPI™ interface. <sup>(2)</sup>			
SI	7	3	I	ST	Data in pin for SPI interface. <sup>(3)</sup>			
SCK	8	4	I	ST	Clock in pin for SPI interface. <sup>(3)</sup>			
CS	9	5	I	ST	Chip select input pin for SPI interface. <sup>(3,4)</sup>			
RESET	10	6	I	ST	Active-low device Reset input. <sup>(3, 4)</sup>			
VSSRX	11	7	Р	_	Ground reference for PHY RX.			
TPIN-	12	8	I	ANA	Differential signal input.			
TPIN+	13	9	I	ANA	Differential signal input.			
RBIAS	14	10	I	ANA	Bias current pin for PHY. Must be tied to VSSRX through a 2 k $\Omega$ , 1% resistor.			
Vddtx	15	11	Р	—	Positive supply for PHY TX.			
TPOUT-	16	12	0	—	Differential signal output.			
TPOUT+	17	13	0	—	Differential signal output.			
Vsstx	18	14	Р	—	Ground reference for PHY TX.			
Vddrx	19	15	Р	—	Positive 3.3V supply for PHY RX.			
VDDPLL	20	16	Р	—	Positive 3.3V supply for PHY PLL.			
VSSPLL	21	17	Р	—	Ground reference for PHY PLL.			
Vssosc	22	18	Р	—	Ground reference for oscillator.			
OSC1	23	19	I	DIG	Oscillator input.			
OSC2	24	20	0	—	Oscillator output.			
VDDOSC	25	21	Р	—	Positive 3.3V supply for oscillator.			
LEDB	26	22	0	—	LEDB driver pin. <sup>(5)</sup>			
LEDA	27	23	0	—	LEDA driver pin. <sup>(5)</sup>			
Vdd	28	24	Р	—	Positive 3.3V supply.			

Legend: I = Input, O = Output, P = Power, DIG = Digital input, ANA = Analog signal input, ST = Schmitt Trigger

**Note 1:** Pins have a maximum current capacity of 8 mA.

2: Pins have a maximum current capacity of 4 mA.

**3:** Pins are 5V tolerant.

4: Pins have an internal weak pull-up to VDD.

5: Pins have a maximum current capacity of 12 mA.

### 2.0 EXTERNAL CONNECTIONS

#### 2.1 Oscillator

The ENC28J60 is designed to operate at 25 MHz with a crystal connected to the OSC1 and OSC2 pins. The ENC28J60 design requires the use of a parallel cut crystal. Use of a series cut crystal may give a frequency out of the crystal manufacturer specifications. A typical oscillator circuit is shown in Figure 2-1.

The ENC28J60 may also be driven by an external clock source connected to the OSC1 pin as shown in Figure 2-2.







FIGURE 2-2: EXTERNAL CLOCK SOURCE<sup>(1)</sup>



#### 2.2 Oscillator Start-up Timer

The ENC28J60 contains an Oscillator Start-up Timer (OST) to ensure that the oscillator and integrated PHY have stabilized before use. The OST does not expire until 7500 OSC1 clock cycles ( $300 \mu$ s) pass after Power-on Reset or wake-up from Power-Down mode occurs. During the delay, all Ethernet registers and buffer memory may still be read and written to through the SPI bus. However, software should not attempt to transmit any packets (set ECON1.TXRTS), enable reception of packets (set ECON1.RXEN) or access any MAC, MII or PHY registers during this period.

When the OST expires, the CLKRDY bit in the ESTAT register will be set. The application software should poll this bit as necessary to determine when normal device operation can begin.

Note: After a Power-on Reset, or the ENC28J60 is removed from Power-Down mode, the CLKRDY bit must be polled before transmitting packets, enabling packet reception or accessing any MAC, MII or PHY registers.


#### 2.3 CLKOUT Pin

The clock out pin is provided to the system designer for use as the host controller clock or as a clock source for other devices in the system. The CLKOUT has an internal prescaler which can divide the output by 1, 2, 3, 4 or 8. The CLKOUT function is enabled and the prescaler is selected via the ECOCON register (Register 2-1).

To create a clean clock signal, the CLKOUT pin is held low for a period when power is first applied. After the Power-on Reset ends, the OST will begin counting. When the OST expires, the CLKOUT pin will begin outputting its default frequency of 6.25 MHz (main clock divided by 4). At any future time that the ENC28J60 is reset by software or the RESET pin, the CLKOUT function will not be altered (ECOCON will not change value). Additionally, Power-Down mode may be entered and the CLKOUT function will continue to operate. When Power-Down mode is cancelled, the OST will be reset but the CLKOUT function will continue. When the CLKOUT function is disabled (ECOCON = 0), the CLKOUT pin is driven low.

The CLKOUT function is designed to ensure that minimum timings are preserved when the CLKOUT pin function is enabled, disabled or the prescaler value is changed. No high or low pulses will be outputted which exceed the frequency specified by the ECOCON configuration. However, when switching frequencies, a delay between two and eight OSC1 clock periods will occur where no clock pulses will be produced (see Figure 2-3). During this period, CLKOUT will be held low.

#### FIGURE 2-3: **CLKOUT TRANSITION**



#### **REGISTER 2-1:** ECOCON: CLOCK OUTPUT CONTROL REGISTER

U-0	U-0	U-0	U-0	U-0	R/W-1	R/W-0	R/W-0
—	—	—	_	—	COCON2	COCON1	COCON0
bit 7							bit 0

bit 7-3 Unimplemented: Read as '0'

bit 2-0 COCON2:COCON0: Clock Output Configuration bits

111 = Reserved for factory test. Do not use. Glitch prevention not assured.

110 = Reserved for factory test. Do not use. Glitch prevention not assured.

101 = CLKOUT outputs main clock divided by 8 (3.125 MHz)

100 = CLKOUT outputs main clock divided by 4 (6.25 MHz)

011 = CLKOUT outputs main clock divided by 3 (8.333333 MHz)

- 010 = CLKOUT outputs main clock divided by 2 (12.5 MHz)
- 001 = CLKOUT outputs main clock divided by 1 (25 MHz)
- 000 = CLKOUT is disabled. The pin is driven low.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

#### 2.4 Magnetics, Termination and Other External Components


To complete the Ethernet interface, the ENC28J60 requires several standard components to be installed externally. These components should be connected as shown in Figure 2-4.

On the differential receive pins (TPIN+/TPIN-), a 1:1 pulse transformer rated for 10BASE-T operation is required. On the differential transmit pins (TPOUT+/TPOUT-), a 1:1 pulse transformer with a center tap is required. The transformers should be rated for isolation of 2 kV or more to protect against static voltages. See Section 16.0 "Electrical Characteristics" for specific transformer requirements. Both portions additionally require two  $50\Omega$ , 1% resistors and a 0.01 µF capacitor for proper termination.

The internal analog circuitry in the ENC28J60 requires that an external  $2 k\Omega$ , 1% resistor be attached from RBIAS to ground.

Some of the digital circuitry in the ENC28J60 operates at a nominal 2.5V to reduce power consumption. A 2.5V regulator is incorporated internally to generate the necessary voltage. The only external component required is a 10  $\mu$ F capacitor for stability purposes. This capacitor should be attached from VCAP to ground. The internal regulator was not designed to drive external loads.

All power supply pins must be externally connected to the same 3.3V power source. Similarly, all ground references should be externally connected to the same ground node. Each VDD and Vss pin pair should have a 0.1  $\mu$ F ceramic bypass capacitor placed as close to the pins as possible. Relatively high currents are necessary to operate the twisted pair interface, so all wires should be kept as short as possible and reasonable wire widths should be used on power wires to reduce resistive loss.



#### FIGURE 2-4: EXTERNAL CONNECTIONS

#### 2.5 I/O Levels

The ENC28J60 is a 3.3V part; however, it was designed to be easily integrated into 5V systems. The SPI CS, SCK and SI inputs, as well as the RESET pin, are all 5V tolerant. On the other hand, if the host controller is operated at 5V, it quite likely will not be within specifications when its SPI and interrupt inputs are driven by the 3.3V CMOS outputs on the ENC28J60. A unidirectional level translator would be necessary.

An economical 74HCT08 (quad AND gate), 74ACT125 (quad 3-state buffer) or many other 5V CMOS chips with TTL level input buffers may be used to provide the necessary level shifting. The use of 3-state buffers permits easy integration into systems which share the SPI bus with other devices. Figure 2-5 and Figure 2-6 show example translation schemes.







FIGURE 2-6:


LEVEL SHIFTING USING 3-STATE BUFFERS




#### 2.6 LED Configuration

The LEDA and LEDB pins support automatic polarity detection on Reset. The LEDs can be connected such that the pin must source current to turn the LED on, or alternately connected such that the pin must sink current to turn the LED on. Upon system Reset, the ENC28J60 will detect how the LED is connected and begin driving the LED to the default state configured by the PHLCON register. If the LED polarity is changed while the ENC28J60 is operating, the new polarity will not be detected until the next system Reset occurs.

LEDB is unique in that the connection of the LED is automatically read on Reset and determines how to initialize the PHCON1.PDPXMD bit. If the pin sources current to illuminate the LED, the bit is cleared on Reset and the PHY defaults to half-duplex operation. If the pin sinks current to illuminate the LED, the bit is set on Reset and the PHY defaults to full-duplex operation. Figure 2-7 shows the two available options. If no LED is attached to the LEDB pin, the PDPXMD bit will reset to an indeterminate value.





#### REGISTER 2-2: PHLCON: PHY MODULE LED CONTROL REGISTER

R/W-0	R/W-0	R/W-1	R/W-1	R/W-0	R/W-1	R/W-0	R/W-0					
r	r	r	r	LACFG3	LACFG2	LACFG1	LACFG0					
bit 15	•	•		L. C.			bit 8					
	R/W-0	R/W-0	R/W-1	R/W-0	R/W-0	R/W-0	R/W-1	R/W-x				
	LBCFG3	LBCFG2	LBCFG1	LBCFG0	LFRQ1	LFRQ0	STRCH	r				
	bit 7						1 1	bit 0				
bit 15-12	Reserved: Write	<b>e as</b> '0'										
bit 11-8	LACFG3:LACF	G0: LEDA Cor	figuration bits									
	0000 = Reserve											
	0001 = Display			)								
	0010 = Display 0011 = Display		· ,	)								
				/								
	0100 = Display link status 0101 = Display duplex status											
	0110 = Reserve											
	0111 = Display transmit and receive activity (stretchable)											
	1000 = On 1001 = Off											
	1001 = OII 1010 = Blink fas	st										
	1011 = Blink slo											
	1100 = Display											
	1101 = Display link status and transmit/receive activity (always stretched)											
	1110 = Display duplex status and collision activity (always stretched) 1111 = Reserved											
bit 7-4	LBCFG3:LBCFG0: LEDB Configuration bits											
DIL 7-4	0000 = Reserved											
	0000 = Reserved 0001 = Display transmit activity (stretchable)											
	0010 = Display											
	0011 = Display		y (stretchable)	)								
	0100 = Display											
	0101 = Display 0110 = Reserve											
	0110 = Reserved 0111 = Display transmit and receive activity (stretchable)											
	1000 = On											
	1001 <b>= Off</b>											
	1010 = Blink fast											
	1011 = Blink slow 1100 = Display link status and receive activity (always stretched)											
	1100 = Display link status and receive activity (always stretched) 1101 = Display link status and transmit/receive activity (always stretched)											
	1110 = Display duplex status and collision activity (always stretched)											
	1111 = Reserved											
bit 3-2	LFRQ1:LFRQ0	: LED Pulse St	retch Time Co	nfiguration bits								
	11 = Reserved 10 = Stretch LED events to approximately 139 ms											
	01 = Stretch LED events to approximately 73 ms 00 = Stretch LED events to approximately 40 ms											
bit 1	STRCH: LED P	•										
	1 = Stretchable 0 = Stretchable	e LED events v	vill cause lengt	•			uration					
bit 0	Reserved: Write	<b>e as</b> '0'										
1.0000-0												
Legend:			\ <b>\</b> /		Deegaadu							
R = Reada	adie dit	W	= Writable bit	r :	= Reserved bit							

R = Readable bit	W = Writable bit	r = Reserved bit	
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

NOTES:

#### 3.0 MEMORY ORGANIZATION

All memory in the ENC28J60 is implemented as static RAM. There are three types of memory in the ENC28J60:


- Control Registers
- Ethernet Buffer
- PHY Registers

The control registers' memory contains Control Registers (CRs). These are used for configuration, control and status retrieval of the ENC28J60. The Control Registers are directly read and written to by the SPI interface.

The Ethernet buffer contains transmit and receive memory used by the Ethernet controller in a single memory space. The sizes of the memory areas are programmable by the host controller using the SPI interface. The Ethernet buffer memory can only be accessed via the read buffer memory and write buffer memory SPI commands (see Section 4.2.2 "Read Buffer Memory Command" and Section 4.2.4 "Write Buffer Memory Command").

The PHY registers are used for configuration, control and status retrieval of the PHY module. The registers are not directly accessible through the SPI interface; they can only be accessed through the Media Independent Interface (MII) implemented in the MAC.

Figure 3-1 shows the data memory organization for the ENC28J60.



#### FIGURE 3-1: ENC28J60 MEMORY ORGANIZATION

#### 3.1 Control Registers

The Control Registers provide the main interface between the host controller and the on-chip Ethernet controller logic. Writing to these registers controls the operation of the interface, while reading the registers allows the host controller to monitor operations.

The Control Register memory is partitioned into four banks, selectable by the bank select bits BSEL1:BSEL0 in the ECON1 register. Each bank is 32 bytes long and addressed by a 5-bit address value.

The last five locations (1Bh to 1Fh) of all banks point to a common set of registers: EIE, EIR, ESTAT, ECON2 and ECON1. These are key registers used in controlling and monitoring the operation of the device. Their common mapping allows easy access without switching the bank. The ECON1 and ECON2 registers are discussed later in this section.

Some of the available addresses are unimplemented. Any attempts to write to these locations are ignored while reads return '0's. The register at address 1Ah in each bank is reserved; read and write operations should not be performed on this register. All other reserved registers may be read, but their contents must not be changed. When reading and writing to registers which contain reserved bits, any rules stated in the register definition should be observed.

Control registers for the ENC28J60 are generically grouped as ETH, MAC and MII registers. Register names starting with "E" belong to the ETH group. Similarly, registers names starting with "MA" belong to the MAC group and registers prefixed with "MI" belong to the MII group.

#### TABLE 3-1: ENC28J60 CONTROL REGISTER MAP

Bank 0		Bank 1		Bank 2		Bank 3	
Address	Name	Address	Name	Address	Name	Address	Name
00h	ERDPTL	00h	EHT0	00h	MACON1	00h	MAADR1
01h	ERDPTH	01h	EHT1	01h	MACON2	01h	MAADR0
02h	EWRPTL	02h	EHT2	02h	MACON3	02h	MAADR3
03h	EWRPTH	03h	EHT3	03h	MACON4	03h	MAADR2
04h	ETXSTL	04h	EHT4	04h	MABBIPG	04h	MAADR5
05h	ETXSTH	05h	EHT5	05h	_	05h	MAADR4
06h	ETXNDL	06h	EHT6	06h	MAIPGL	06h	EBSTSD
07h	ETXNDH	07h	EHT7	07h	MAIPGH	07h	EBSTCON
08h	ERXSTL	08h	EPMM0	08h	MACLCON1	08h	EBSTCSL
09h	ERXSTH	09h	EPMM1	09h	MACLCON2	09h	EBSTCSH
0Ah	ERXNDL	0Ah	EPMM2	0Ah	MAMXFLL	0Ah	MISTAT
0Bh	ERXNDH	0Bh	EPMM3	0Bh	MAMXFLH	0Bh	_
0Ch	ERXRDPTL	0Ch	EPMM4	0Ch	Reserved	0Ch	—
0Dh	ERXRDPTH	0Dh	EPMM5	0Dh	MAPHSUP	0Dh	—
0Eh	ERXWRPTL	0Eh	EPMM6	0Eh	Reserved	0Eh	—
0Fh	ERXWRPTH	0Fh	EPMM7	0Fh	—	0Fh	—
10h	EDMASTL	10h	EPMCSL	10h	Reserved	10h	—
11h	EDMASTH	11h	EPMCSH	11h	MICON	11h	—
12h	EDMANDL	12h	—	12h	MICMD	12h	EREVID
13h	EDMANDH	13h	—	13h	_	13h	_
14h	EDMADSTL	14h	EPMOL	14h	MIREGADR	14h	_
15h	EDMADSTH	15h	EPMOH	15h	Reserved	15h	ECOCON
16h	EDMACSL	16h	EWOLIE	16h	MIWRL	16h	Reserved
17h	EDMACSH	17h	EWOLIR	17h	MIWRH	17h	EFLOCON
18h	—	18h	ERXFCON	18h	MIRDL	18h	EPAUSL
19h	—	19h	EPKTCNT	19h	MIRDH	19h	EPAUSH
1Ah	Reserved	1Ah	Reserved	1Ah	Reserved	1Ah	Reserved
1Bh	EIE	1Bh	EIE	1Bh	EIE	1Bh	EIE
1Ch	EIR	1Ch	EIR	1Ch	EIR	1Ch	EIR
1Dh	ESTAT	1Dh	ESTAT	1Dh	ESTAT	1Dh	ESTAT
1Eh	ECON2	1Eh	ECON2	1Eh	ECON2	1Eh	ECON2
1Fh	ECON1	1Fh	ECON1	1Fh	ECON1	1Fh	ECON1

Register Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on	Details on		
									Reset	Page		
EIE	INTIE	PKTIE	DMAIE	LINKIE	TXIE	WOLIE	TXERIE	RXERIE	0000 0000	67		
EIR	—	PKTIF	DMAIF	LINKIF	TXIF	WOLIF	TXERIF	RXERIF	-000 0000	68		
ESTAT	INT	r	r	LATECOL	—	RXBUSY	TXABRT	CLKRDY <sup>(1)</sup>	0000 -000	66		
ECON2	AUTOINC	PKTDEC	PWRSV	—	VRPS	_	_	_	100- 0	16		
ECON1	TXRST	TXRST RXRST DMAST CSUMEN TXRTS RXEN BSEL1 BSEL0										
ERDPTL	Read Pointe	ad Pointer Low Byte ERDPT<7:0>)										
ERDPTH	—	— — Read Pointer High Byte (ERDPT<12:8>)										
EWRPTL	Write Pointe	er Low Byte (	EWRPT<7:0>	)					0000 0000	17		
EWRPTH	—	-	—	Write Pointer	High Byte (EV	VRPT<12:8>)			0 0000	17		
ETXSTL	TX Start Lov	w Byte (ETXS	ST<7:0>)						0000 0000	17		
ETXSTH	_		_	TX Start High	n Byte (ETXST	(<12:8>)			0 0000	17		
ETXNDL	TX End Low	/ Byte (ETXN	ID<7:0>)						0000 0000	17		
ETXNDH	—	—	_	TX End High	Byte (ETXND	<12:8>)			0 0000	17		
ERXSTL	RX Start Lov	w Byte (ERX	ST<7:0>)						1111 1010	17		
ERXSTH	—	—	—	RX Start High	n Byte (ERXSI	「<12:8>)			0 0101	17		
ERXNDL	RX End Lov	v Byte (ERXN	ND<7:0>)	•					1111 1111	17		
ERXNDH	—	—	—	RX End High	Byte (ERXND	<12:8>)			1 1111	17		
ERXRDPTL	RX RD Poir	ter Low Byte	(ERXRDPT<	7:0>)					1111 1010	17		
ERXRDPTH	_	_	_	RX RD Point	er High Byte (I	ERXRDPT<12:8	3>)		0 0101	17		
ERXWRPTL	RX WR Pointer Low Byte (ERXWRPT<7:0>)								0000 0000	17		
ERXWRPTH	RX WR Pointer High Byte (ERXWRPT<12:8>)									17		
EDMASTL	DMA Start Low Byte (EDMAST<7:0>)									75		
EDMASTH	— — — DMA Start High Byte (EDMAST<12:8>)								0 0000	75		
EDMANDL	DMA End Low Byte (EDMAND<7:0>)								0000 0000	75		
EDMANDH	_	_	_	DMA End Hig	gh Byte (EDM	AND<12:8>)			0 0000	75		
EDMADSTL	DMA Destin	ation Low By	/te (EDMADS			,			0000 0000	75		
EDMADSTH	_	_	_	DMA Destina	ation High Byte	e (EDMADST<1	2:8>)		0 0000	75		
EDMACSL	DMA Check	sum Low By	te (EDMACS<	:7:0>)		,	,		0000 0000	76		
EDMACSH	DMA Check	sum High By	te (EDMACS	<15:8>)					0000 0000	76		
EHT0		Byte 0 (EHT-	· ·	,					0000 0000	52		
EHT1		Byte 1 (EHT							0000 0000	52		
EHT2	Hash Table	Byte 2 (EHT	<23:16>)						0000 0000	52		
EHT3		Byte 3 (EHT							0000 0000	52		
EHT4		Byte 4 (EHT	-						0000 0000	52		
EHT5		Byte 5 (EHT-							0000 0000	52		
EHT6		Byte 6 (EHT-	,						0000 0000	52		
EHT7		Byte 7 (EHT	,						0000 0000	52		
EPMM0		<i>,</i> ,	e 0 (EPMM<7:	0>)					0000 0000	51		
EPMM1		,	e 1 (EPMM<1	,					0000 0000	51		
EPMM2			e 2 (EPMM<23	,					0000 0000	51		
EPMM3		,	e 3 (EPMM<3'	/					0000 0000	51		
EPMM4		,	e 4 (EPMM<39	/					0000 0000	51		
EPMM5			e 5 (EPMM<47	,					0000 0000	51		
EPMM6		,	e 6 (EPMM<5	/					0000 0000	51		
EPMM7		,	e 7 (EPMM<6	/					0000 0000	51		
EPMCSL		,		,					0000 0000	51		
EPMCSH	Pattern Match Checksum Low Byte (EPMCS<7:0>) 0 Pattern Match Checksum High Byte (EPMCS<15:0>) 0									51		

...... .....

x = unknown, u = unchanged, — = unimplemented, q = value depends on condition, r = reserved, do not modify. Legend:

Note 1: CLKRDY resets to '0' on Power-on Reset but is unaffected on all other Resets.

EREVID is a read-only register. 2:

3: ECOCON resets to '---- -100' on Power-on Reset and '---- -uuu' on all other Resets.

Register Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on Reset	Details on Page
EPMOL	Pattern Mat	ch Offset Lov	w Byte (EPMO	<7:0>)					0000 0000	51
EPMOH	—	— — Pattern Match Offset High Byte (EPMO<12:8>)								
EWOLIE	UCWOLIE	AWOLIE	_	PMWOLIE	MPWOLIE	HTWOLIE	MCWOLIE	BCWOLIE	00-0 0000	72
EWOLIR	UCWOLIF	AWOLIF	_	PMWOLIF	MPWOLIF	HTWOLIF	MCWOLIF	BCWOLIF	00-0 0000	73
ERXFCON	UCEN	ANDOR	CRCEN	PMEN	MPEN	HTEN	MCEN	BCEN	1010 0001	48
EPKTCNT	Ethernet Pa		0000 0000	43						
MACON1	_	_	_	LOOPBK	TXPAUS	RXPAUS	PASSALL	MARXEN	0 0000	34
MACON2	MARST	RNDRST	_	_	MARXRST	RFUNRST	MATXRST	TFUNRST	10 0000	61
MACON3	PADCFG2	PADCFG1	PADCFG0	TXCRCEN	PHDRLEN	HFRMEN	FRMLNEN	FULDPX	0000 0000	35
MACON4	—	DEFER	BPEN	NOBKOFF	_	—	LONGPRE	PUREPRE	-00000	36
MABBIPG	_	Back-to-Bac	k Inter-Packet	Gap (BBIPG	<6:0>)				-000 0000	37
MAIPGL	<ul> <li>Non-Back-to-Back Inter-Packet Gap Low Byte (MAIPGL&lt;6:0&gt;)</li> </ul>									34
MAIPGH	_	Non-Back-to	-Back Inter-Pa	acket Gap Hig	h Byte (MAIPG	GH<6:0>)			-000 0000	34
MACLCON1	_	_	_	_	Retransmissio	on Maximum (R	ETMAX<3:0>)		1111	34
MACLCON2	— — Collision Window (COLWIN<5:0>)								11 0111	34
MAMXFLL	Maximum Frame Length Low Byte (MAMXFL<7:0>)								0000 0000	34
MAMXFLH	Maximum Frame Length High Byte (MAMXFL<15:8>)								0000 0110	34
MAPHSUP	RSTINTFC	—	—	r	RSTRMII	—	—	r	01 00	62
MICON	RSTMI	_	_	_	_	_	_	_	0	21
MICMD	_	_	_	_	_	_	MIISCAN	MIIRD	00	21
MIREGADR	_	_	_	MII Register	Address (MIRE	GADR<4:0>)			0 0000	19
MIWRL	MII Write Da	ata Low Byte	(MIWR<7:0>)						0000 0000	19
MIWRH	MII Write Da	ata High Byte	e (MIWR<15:8:	>)					0000 0000	19
MIRDL	MII Read Da	ata Low Byte	(MIRD<7:0>)						0000 0000	19
MIRDH	MII Read Da	ata High Byte	e(MIRD<15:8>	)					0000 0000	19
MAADR1	MAC Addre	ss Byte 1 (M	AADR<15:8>)						0000 0000	34
MAADR0	MAC Addre	ss Byte 0 (M	AADR<7:0>)						0000 0000	34
MAADR3	MAC Addre	ss Byte 3 (M	AADR<31:24>	·)					0000 0000	34
MAADR2	MAC Addre	ss Byte 2(MA	ADR<23:16>)	)					0000 0000	34
MAADR5	MAC Addre	ss Byte 5 (M	AADR<48:41>	·)					0000 0000	34
MAADR4	MAC Addre	ss Byte 4 (M	AADR<40:32>	·)					0000 0000	34
EBSTSD	Built-in Self	-Test Fill See	d (EBSTSD<7	(<0>)					0000 0000	80
EBSTCON	PSV2	PSV1	PSV0	PSEL	TMSEL1	TMSEL0	TME	BISTST	0000 0000	79
EBSTCSL	Built-in Self	- Test Checks	um Low Byte	EBSTCS<7:0	)>)		•	•	0000 0000	80
EBSTCSH	Built-in Self	-Test Checks	um High Byte	(EBSTCS<15	:8>)				0000 0000	80
MISTAT	—	_	_	—	r	NVALID	SCAN	BUSY	0000	22
EREVID <sup>(2)</sup>	_	_	_	Ethernet Rev	ision ID (ERE	/ID<4:0>)	•	•	d dddd	22
ECOCON <sup>(3)</sup>	_	_	_	_	_	COCON2	COCON1	COCON0	100	6
EFLOCON	_	_	_	_	_	FULDPXS	FCEN1	FCEN0	000	56
EPAUSL	Pause Time	r Value Low	Byte (EPAUS<	<7:0>)					0000 0000	57
EPAUSH	Pause Time	r Value High	Byte (EPAUS	<15:8>)					0001 0000	57

#### ENC28 160 CONTROL REGISTER SUMMARY (CONTINUED)

Legend: Note

x = unknown, u = unchanged, — = unimplemented, q = value depends on condition, r = reserved, do not modify. CLKRDY resets to '0' on Power-on Reset but is unaffected on all other Resets.

1:

2: EREVID is a read-only register.

3: ECOCON resets to '---- -100' on Power-on Reset and '---- -uuu' on all other Resets.

#### 3.1.1 ECON1 REGISTER

The ECON1 register, shown in Register 3-1, is used to control the main functions of the ENC28J60. Receive enable, transmit request, DMA control and bank select bits can all be found in ECON1.

#### REGISTER 3-1: ECON1: ETHERNET CONTROL REGISTER 1

IR 3-1:	ECONT: ETHERNET CONTROL REGISTER T										
	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0			
	TXRST	RXRST	DMAST	CSUMEN	TXRTS	RXEN	BSEL1	BSEL0			
	bit 7 bit 0										
bit 7		ansmit Logio									
		mit logic is h									
0 = Normal operation											
bit 6		eceive Logic									
<ul><li>1 = Receive logic is held in Reset</li><li>0 = Normal operation</li></ul>											
h:4 /		-									
bit 5	DMAST: DMA Start and Busy Status bit <ol> <li>DMA copy or checksum operation is in progress</li> </ol>										
		hardware is		luon is in pro	gress						
bit 4	CSUMEN: DMA Checksum Enable bit										
		hardware ca									
	0 = DMA hardware copies buffer memory										
bit 3	TXRTS: Tr	ransmit Requ	uest To Sen	d bit							
				g to transmit	a packet						
	0 = The tr	ansmit logic	is Idle								
bit 2		ceive Enable									
				nt filter config	juration will	be written i	nto the recei	ve buffer			
1.1.4.0	•	ckets receive	0	nored							
bit 1-0		SEL0: Bank									
		iccesses reg iccesses reg									
		iccesses reg									
		iccesses reg									
	Legend:										
	R = Readable bit $W$ = Writable bit $U$ = Unimplemented bit, read as '0'										
	-n = Value		'1' = B		(a) D:/ .	s cleared	x = Bit is u				

#### 3.1.2 ECON2 REGISTER

The ECON2 register, shown in Register 3-2, is used to control other main functions of the ENC28J60.

<b>REGISTER 3-2:</b>	ECON2: ETHERNET CONTROL REGISTER 2								
	R/W-1	W-0	R/W-0	U-0	R/W-0	U-0	U-0	U-0	
	AUTOINC	PKTDEC	PWRSV		VRPS	—	—		
	bit 7							bit 0	
bit 7 <b>AUTOINC:</b> Automatic Buffer Pointer Increment Enable bit									
Sitt	<ul> <li>1 = Automatically increment ERDPT and EWRPT when the SPI RBM/WBM command is used</li> <li>0 = Do not automatically change ERDPT and EWRPT after the buffer is accessed</li> </ul>								
bit 6	PKTDEC: Packet Decrement bit 1 = Decrement the EPKTCNT register by one 0 = Leave EPKTCNT unchanged								
bit 5	<b>PWRSV:</b> Power Save Enable bit 1 = MAC, PHY and control logic are in Low-Power Sleep mode 0 = Normal operation								
bit 4	Unimplem	ented: Read	<b>as</b> '0'						
bit 3	<ul> <li>VRPS: Voltage Regulator Power Save Enable bit</li> <li><u>When PWRSV = 1:</u></li> <li>1 = Internal voltage regulator is in Low-Current mode</li> <li>0 = Internal voltage regulator is in Normal Current mode</li> <li><u>When PWRSV = 0:</u></li> <li>The bit is ignored; the regulator always outputs as much current as the device requires.</li> </ul>								
bit 2-0	Unimplem	ented: Read	<b>l as</b> '0'						

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
- n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

#### 3.2 Ethernet Buffer

The Ethernet buffer contains transmit and receive memory used by the Ethernet controller. The entire buffer is 8 Kbytes, divided into separate receive and transmit buffer spaces. The sizes and locations of transmit and receive memory are fully programmable by the host controller using the SPI interface.

The relationship of the buffer spaces is shown in Figure 3-2.

#### 3.2.1 RECEIVE BUFFER

The receive buffer constitutes a circular FIFO buffer managed by hardware. The register pairs ERXSTH:ERXSTL and ERXNDH:ERXNDL serve as pointers to define the buffer's size and location within the memory. The byte pointed to by ERXST and the byte pointed to by ERXND are both included in the FIFO buffer.

As bytes of data are received from the Ethernet interface, they are written into the receive buffer sequentially. However, after the memory pointed to by ERXND is written to, the hardware will automatically write the next byte of received data to the memory pointed to by ERXST. As a result, the receive hardware will never write outside the boundaries of the FIFO.

The host controller may program the ERXST and ERXND pointers when the receive logic is not enabled. The pointers must not be modified while the receive logic is enabled (ECON1.RXEN is set). If desired, the pointers may span the 1FFFh to 0000h memory boundary; the hardware will still operate as a FIFO.

The ERXWRPTH:ERXWRPTL registers define a location within the FIFO where the hardware will write bytes that it receives. The pointer is read-only and is automatically updated by the hardware whenever a new packet is successfully received. The pointer is useful for determining how much free space is available within the FIFO.

The ERXRDPT registers define a location within the FIFO where the receive hardware is forbidden to write to. In normal operation, the receive hardware will write data up to, but not including, the memory pointed to by ERXRDPT. If the FIFO fills up with data and new data continues to arrive, the hardware will not overwrite the previously received data. Instead, the new data will be thrown away and the old data will be preserved. In order to continuously receive new data, the host controller must periodically advance this pointer whenever it finishes processing some, or all, of the old received data.

#### 3.2.2 TRANSMIT BUFFER

Any space within the 8-Kbyte memory, which is not programmed as part of the receive FIFO buffer, is considered to be the transmit buffer. The responsibility of managing where packets are located in the transmit buffer belongs to the host controller. Whenever the host controller decides to transmit a packet, the ETXST and ETXND pointers are programmed with addresses specifying where, within the transmit buffer, the particular packet to transmit is located. The hardware does not check that the start and end addresses do not overlap with the receive buffer. To prevent buffer corruption, the host controller must make sure to not transmit a packet while the ETXST and ETXND pointers are overlapping the receive buffer, or while the ETXND pointer is too close to the receive buffer. See Section 7.1 "Transmitting Packets" for more information.

## 3.2.3 READING AND WRITING TO THE BUFFER


The Ethernet buffer contents are accessed from the host controller though separate read and write pointers (ERDPT and EWRPT) combined with the read buffer memory and write buffer memory SPI commands. While sequentially reading from the receive buffer, a wrapping condition will occur at the end of the receive buffer. While sequentially writing to the buffer, no wrapping conditions will occur. See Section 4.2.2 "Read Buffer Memory Command" and Section 4.2.4 "Write Buffer Memory Command" for more information.

#### 3.2.4 DMA ACCESS TO THE BUFFER

The integrated DMA controller must read from the buffer when calculating a checksum and it must read and write to the buffer when copying memory. The DMA follows the same wrapping rules that SPI accesses do. While it sequentially reads, it will be subject to a wrapping condition at the end of the receive buffer. All writes it does will not be subject to any wrapping conditions. See **Section 13.0 "Direct Memory Access Controller"** for more information.

# **ENC28J60**

#### FIGURE 3-2: ETHERNET BUFFER ORGANIZATION



#### 3.3 PHY Registers

The PHY registers provide configuration and control of the PHY module, as well as status information about its operation. All PHY registers are 16 bits in width. There are a total of 32 PHY addresses; however, only 9 locations are implemented. Writes to unimplemented locations are ignored and any attempts to read these locations will return '0'. All reserved locations should be written as '0'; their contents should be ignored when read.

Unlike the ETH, MAC and MII control registers, or the buffer memory, the PHY registers are not directly accessible through the SPI control interface. Instead, access is accomplished through a special set of MAC control registers that implement a Media Independent Interface for Management (MIIM). These control registers are referred to as the MII registers. The registers that control access to the PHY registers are shown in Register 3-3 and Register 3-4.

#### 3.3.1 READING PHY REGISTERS

When a PHY register is read, the entire 16 bits are obtained.

To read from a PHY register:

- 1. Write the address of the PHY register to read from into the MIREGADR register.
- 2. Set the MICMD.MIIRD bit. The read operation begins and the MISTAT.BUSY bit is set.
- 3. Wait 10.24  $\mu$ s. Poll the MISTAT.BUSY bit to be certain that the operation is complete. While busy, the host controller should not start any MIISCAN operations or write to the MIWRH register.

When the MAC has obtained the register contents, the BUSY bit will clear itself.

- 4. Clear the MICMD.MIIRD bit.
- 5. Read the desired data from the MIRDL and MIRDH registers. The order that these bytes are accessed is unimportant.

#### 3.3.2 WRITING PHY REGISTERS

When a PHY register is written to, the entire 16 bits is written at once; selective bit writes are not implemented. If it is necessary to reprogram only select bits in the register, the controller must first read the PHY register, modify the resulting data and then write the data back to the PHY register. To write to a PHY register:

- 1. Write the address of the PHY register to write to into the MIREGADR register.
- 2. Write the lower 8 bits of data to write into the MIWRL register.
- Write the upper 8 bits of data to write into the MIWRH register. Writing to this register automatically begins the MII transaction, so it must be written to after MIWRL. The MISTAT.BUSY bit becomes set.

The PHY register will be written after the MII operation completes, which takes  $10.24 \,\mu$ s. When the write operation has completed, the BUSY bit will clear itself. The host controller should not start any MIISCAN or MIIRD operations while busy.

#### 3.3.3 SCANNING A PHY REGISTER

The MAC can be configured to perform automatic back-to-back read operations on a PHY register. This can significantly reduce the host controller complexity when periodic status information updates are desired. To perform the scan operation:


- 1. Write the address of the PHY register to read from into the MIREGADR register.
- Set the MICMD.MIISCAN bit. The scan operation begins and the MISTAT.BUSY bit is set. The first read operation will complete after 10.24 μs. Subsequent reads will be done at the same interval until the operation is cancelled. The MISTAT.NVALID bit may be polled to determine when the first read operation is complete.

After setting the MIISCAN bit, the MIRDL and MIRDH registers will automatically be updated every  $10.24 \,\mu$ s. There is no status information which can be used to determine when the MIRD registers are updated. Since the host controller can only read one MII register at a time through the SPI, it must not be assumed that the values of MIRDL and MIRDH were read from the PHY at exactly the same time.

When the MIISCAN operation is in progress, the host controller must not attempt to write to MIWRH or start an MIIRD operation. The MIISCAN operation can be cancelled by clearing the MICMD.MIISCAN bit and then polling the MISTAT.BUSY bit. New operations may be started after the BUSY bit is cleared.

TAB	TABLE 3-3:	ENC	ENC28J60 PHY REGISTER SUMMARY	HY RE	GISTER	SUMM	ARY											
Addr	Name	Bit 15	Bit 14	Bit 13	Bit 12	Bit 11	Bit 10	Bit 9	Bit 8	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values
400	PHCON1	PRST	PLOOPBK	I		PPWRSV	-	I	PDPXMD <sup>(1)</sup>	-	1	I		I		I	1	00 10-q 0
01h	PHSTAT1	Ι	Ι	Ι	PFDPX	ХАДНА		-	Ι						LLSTAT	JBSTAT	I	1 100-
02h	PHID1	PHY Ident	PHY Identifier (PID18:PID3) = 0083h	300 = (ECIc	33h													0000 0000 1000 0011
03h	PHID2	PHY Ident	PHY Identifier (PID24:PID19) = 000101	31D19) = 00	10101			400 = (ONAG:3NAG) N/G YHG	N5:PPN0) = (	HOC				PHY Rev	vision (PR	PHY Revision (PREV3:PREV0) = 00h	400 = (0,	0001 0100 0000 0000
10h	<b>PHCON2</b>	Ι	FRCLNK	TXDIS	-	-	JABBER	-	SIGTOH	-	-	-	-	-	-	-	-	-000 0000 0000 -
11h	PHSTAT2	Ι	Ι	TXSTAT		RXSTAT COLSTAT	LSTAT	DP XSTAT <sup>(1)</sup>	-				PLRITY	Ι			I	0 00d
12h	PHIE	L	-	-	-	-	-	-	-	L	-	-	PLNKIE	L	L	PGEIE	-	0000 0000 0000 0000
13h	PHIR	r	r	L	r	r	L	r	r	r	r	r	PLNKIF	L	PGIF	r	L	XXXX XXXX XX00 00X0
14h	PHLCON	L	L	L	L	LACFG3:LACFG0	ACFG0			LBCFG3.	BCFG3:LBCFG0		1	LFRQ1:L	FRQ1:LFRQ0	STRCH	L	x100 0010 0010 001x
Legend: Note 1:		unknown, <sub>1</sub> ∍t values oi	${\bf x}$ = unknown, ${\bf u}$ = unchanged, — = unimplemented, ${\bf q}$ = val Reset values of the Duplex mode/status bits depend on the	ed, — = un mode/stati	iimplement∈ us bits dep∈	ed,	e depends onnection	x = unknown, $u = unchanged$ , $m = unimplemented$ , $q = value depends on condition$ , $r = reserved$ , do not modify. Reset values of the Duplex mode/status bits depend on the connection of the LED to the LEDB pin (see <b>Section 2.6 "LED Configuration"</b> for additional details).	r = reserved the LEDB pi	, do not π n (see <b>Se</b>	nodify. ction 2.6	"LED Co	nfigurati	on" for 6	additional	details).		

## **ENC28J60**



#### REGISTER 3-4: MICMD: MII COMMAND REGISTER

U-0	U-0	U-0	U-0	U-0	U-0	R/W-0	R/W-0
	—	—	_	—		MIISCAN	MIIRD
bit 7							bit 0

#### bit 7-2 Unimplemented: Read as '0'

bit 1 MIISCAN: MII Scan Enable bit

PHY register at MIREGADR is continously read and the data is placed in MIRD
 No MII management scan operation is in progress

#### bit 0 MIIRD: MII Read Enable bit

1 = PHY register at MIREGADR is read once and the data is placed in MIRD

0 = No MII management read operation is in progress

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

## **ENC28J60**

REGISTER 3-5:	MISTAT: MI	I STATUS	REGISTE	R				
	U-0	U-0	U-0	U-0	R-0	R-0	R-0	R-0
	—	_	—	_	r	NVALID	SCAN	BUSY
	bit 7					·		bit 0
bit 7-4	Unimpleme	nted: Read	<b>d as</b> '0'					
bit 3	Reserved:	Maintain '0'						
bit 1	NVALID: MI	I Managem	ent Read D	ata Not Valio	d bit			
	1 = The cor 0 = The MII			•	leted and N	/IRD has bee	en updated	
bit 1	SCAN: MIL	Manageme	nt Scan Ope	eration bit				
	1 = MII mar 0 = No MII i	•	•					
bit 0	BUSY: MIL	<i>l</i> lanageme	nt Busy bit					
	1 = A PHY 0 = The MII	•	•	•	ritten to			
	Legend:							
	R = Readab	le bit	r = reserved	d, maintain a	as '0' U = L	Inimplemente	ed bit, read	as '0'
	-n = Value a	t POR	'1' = Bit is s	et	'0' = I	Bit is cleared	x = Bit i	s unknown

#### 3.3.4 PHSTAT REGISTERS

The PHSTAT1 and PHSTAT2 registers contain readonly bits that show the current status of the PHY module's operations, particularly the conditions of the communications link to the rest of the network.

The PHSTAT1 register (Register 3-6) contains the LLSTAT bit; it clears and latches low if the physical layer link has gone down since the last read of the register. Periodic polling by the host controller can be used to determine exactly when the link fails. It may be particularly useful if the link change interrupt is not used.

The PHSTAT1 register also contains a jabber status bit. An Ethernet controller is said to be "jabbering" if it continuously transmits data without stopping and allowing other nodes to share the medium. Generally, the jabber condition indicates that the local controller may be grossly violating the maximum packet size defined by the IEEE specification. This bit latches high to indicate that a jabber condition has occurred since the last read of the register.

The PHSTAT2 register (Register 3-7) contains status bits which report if the PHY module is linked to the network and whether or not it is transmitting or receiving.

#### 3.3.5 PHID1 AND PHID2 REGISTERS

The PHID1 and PHID2 registers are read-only registers. They hold constant data that help identify the Ethernet controller and may be useful for debugging purposes. This includes:

- The part number of the PHY module (PPN5:PPN0)
- The revision level of the PHY module (PREV3:PREV0); and
- The PHY Identifier, as part of Microchip's corporate Organizationally Unique Identifier (OUI) (PID24:PID3)

The PHY part number and revision are part of PHID2. The upper two bytes of the PHY identifier are located in PHID1, with the remainder in PHID2. The exact locations within registers are shown in Table 3-3.

Revision information is also stored in EREVID. This is a read-only control register which contains a 5-bit identifier for the specific silicon revision level of the device. Details of this register are shown in Table 3-2.

REGISTI	ER 3-6: Pł	ISTAT1: P	HYSICAL LA	YER STAT	JS REGIST	ER 1		
U-0	U-0	U-0	R-1	R-1	U-0	U-0	U-0	
	—	_	PFDPX	PHDPX		_		
bit 15							bit 8	
	U-0	) U-	0 U-0	U-0	U-0	R/LL-0	R/LH-0	U-0
					_	LLSTAT	JBRSTAT	
	bit 7							bit 0
bit 15-13 bit 12	Unimplement PFDPX: PHY 1 = PHY is ca	Full-Duplex	Capable bit	1bps in Full-Du	uplex mode (	this bit is alway	ays set)	
bit 11	<b>PHDPX:</b> PHY 1 = PHY is ca	•	·	lbps in Half-D	uplex mode	(this bit is alw	ays set)	
bit 10-3	Unimplement	ed: Read as	<b>s</b> '0'					
bit 2	LLSTAT: PHY	Latching Li	nk Status bit					
	1 = Link is up 0 = Link is do							
bit 1	JBRSTAT: PH	•						
	1 = PHY has 0 = PHY has						AT1 was last re ast read	ad
bit 0	Unimplement	ed: Read as	<b>s</b> 'O'					
Legend:								

Legena.			
R = Read-only bit	R/L = Read-only latch bit	U = Unimplemented bit, rea	ad as '0'
'1' = Bit is set on POR	'0' = Bit is cleared on POR	LL = Bit latches low	LH = Bit latches high

U-0	U-0	R-0	R-0	R-0	R-0	R-x	U-0						
_	_	TXSTAT	RXSTAT	COLSTAT	LSTAT	DPXSTAT <sup>(1)</sup>							
oit 15				<u> </u>		I	bit	8					
	U-0	U-0	U-0	R-0	U-0	U-0	U-0	U-0					
		_	_	PLRITY	—	_	_	—					
	bit 7				1			bit (					
oit 15-14	Unimplemente	ed: Read as '	0'										
bit 13	TXSTAT: PHY	Transmit Stat	us bit										
	1 = PHY is trai	•											
	0 = PHY is not	•											
oit 12	RXSTAT: PHY		us bit										
	1 = PHY is rec 0 = PHY is not	U U	ta										
oit 11	COLSTAT: PHY Collision Status bit												
	1 = A collision is occuring												
	0 = A collision	is not occurir	ng										
oit 10	LSTAT: PHY Li	nk Status bit	(non-latching)										
	1 = Link is up	<i>1</i> 0											
oit 9	0 = Link is dov DPXSTAT: PH		uc hit(1)										
JIL 9	1 = PHY is cor			ation (PHCON		) is set)							
	0 = PHY is cor												
			•	ode/status bits	•	the connection al details).	of the LED to	the LEDE					
bit 8-5	Unimplemente	ed: Read as '	0'										
oit 4	PLRITY: Polari	ty Status bit											
	1 = The polarit												
	0 = The polarit	y of the signa	al on TPIN+/11	PIN- is correct									
bit 3-0	Unimplemente												

U = Unimplemented bit, read as '0'

'0' = Bit is cleared

R = Readable bit

-n = Value at POR

W = Writable bit

'1' = Bit is set


x = Bit is unknown

### 4.0 SERIAL PERIPHERAL INTERFACE (SPI)


#### 4.1 Overview

The ENC28J60 is designed to interface directly with the Serial Peripheral Interface (SPI) port available on many microcontrollers. The implementation used on this device supports SPI mode 0,0 only. In addition, the SPI port requires that SCK be at Idle in a low state; selectable clock polarity is not supported.

#### FIGURE 4-1: SPI™ INPUT TIMING



#### FIGURE 4-2: SPI™ OUTPUT TIMING



Commands and data are sent to the device via the SI pin, with data being clocked in on the rising edge of SCK. Data is driven out by the ENC28J60 on the SO line, on the falling edge of SCK. The CS pin must be held low while any operation is performed and returned high when finished.

#### 4.2 SPI Instruction Set

The operation of the ENC28J60 depends entirely on commands given by an external host controller over the SPI interface. These commands take the form of instructions, of one or more bytes, which are used to access the control memory and Ethernet buffer spaces. At the least, instructions consist of a 3-bit opcode,

followed by a 5-bit argument that specifies either a register address or a data constant. Write and bit field instructions are also followed by one or more bytes of data.

A total of seven instructions are implemented on the ENC28J60. Table 4-1 shows the command codes for all operations.

TABLE 4-1:	SPI™ INSTRUCTION SET FOR THE ENC28J60

Instruction				By	te 0					By	te 1	and	Fol	low	ing	
Name and Mnemonic	0	рсос	de		Ar	gum	ent					Da	ata			
Read Control Register (RCR)	0	0	0	a	a	a	a	a				N	/A			
Read Buffer Memory (RBM)	0	0	1	1	1	0	1	0				N	/A			
Write Control Register (WCR)	0	1	0	a	a	a	a	a	d	d	d	d	d	d	d	d
Write Buffer Memory (WBM)	0	1	1	1	1	0	1	0	d	d	d	d	d	d	d	d
Bit Field Set (BFS)	1	0	0	a	a	a	a	a	d	d	d	d	d	d	d	d
Bit Field Clear (BFC)	1	0	1	a	a	a	a	a	d	d	d	d	d	d	d	d
System Command (Soft Reset) (SC)	1	1	1	1	1	1	1	1				N	/A			

**Legend:** a = control register address, d = data payload.


### 4.2.1 READ CONTROL REGISTER COMMAND

The Read Control Register (RCR) command allows the host controller to read any of the ETH, MAC and MII registers in any order. The contents of the PHY registers are read via a special MII register interface (see **Section 3.3.1 "Reading PHY Registers"** for more information).


The RCR command is started by pulling the  $\overline{CS}$  pin low. The RCR opcode is then sent to the ENC28J60, followed by a 5-bit register address (A4 through A0). The 5-bit address identifies any of the 32 control registers in the current bank. If the 5-bit address is an ETH register, then data in the selected register will immediately start shifting out MSb first on the SO pin. Figure 4-3 shows the read sequence for these registers.

If the address specifies one of the MAC or MII registers, a dummy byte will first be shifted out the SO pin. After the dummy byte, the data will be shifted out MSb first on the SO pin. The RCR operation is terminated by raising the  $\overline{CS}$  pin. Figure 4-4 shows the read sequence for MAC and MII registers.

FIGURE 4-3: READ CONTROL REGISTER COMMAND SEQUENCE (ETH REGISTERS)



## FIGURE 4-4: READ CONTROL REGISTER COMMAND SEQUENCE (MAC AND MII REGISTERS)



#### 4.2.2 READ BUFFER MEMORY COMMAND

The Read Buffer Memory (RBM) command allows the host controller to read bytes from the integrated 8-Kbyte transmit and receive buffer memory.

If the AUTOINC bit in the ECON2 register is set, the ERDPT pointer will automatically increment to point to the next address after the last bit of each byte is read. The next address will normally be the current address incremented by one. However, if the last byte in the receive buffer is read (ERDPT = ERXND), the ERDPT pointer will change to the beginning of the receive buffer (ERXST). This allows the host controller to read packets from the receive buffer in a continuous stream without keeping track of when a wraparound is needed. If AUTOINC is set when address 1FFFh is read and ERXND does not point to this address, the read pointer will increment and wrap around to 0000h.


The RBM command is started by pulling the  $\overline{CS}$  pin low. The RBM opcode is then sent to the ENC28J60, followed by the 5-bit constant 1Ah. After the RBM command and constant are sent, the data stored in the memory pointed to by ERDPT will be shifted out MSb first on the SO pin. If the host controller continues to provide clocks on the SCK pin, without raising  $\overline{CS}$ , the byte pointed to by ERDPT will again be shifted out MSb first on the SO pin. In this manner, with AUTOINC enabled, it is possible to continuously read sequential bytes from the buffer memory without any extra SPI command overhead. The RBM command is terminated by raising the  $\overline{CS}$  pin.

#### 4.2.3 WRITE CONTROL REGISTER COMMAND

The Write Control Register (WCR) command allows the host controller to write to any of the ETH, MAC and MII Control registers in any order. The PHY registers are written to via a special MII register interface (see **Section 3.3.2 "Writing PHY Registers**" for more information).

The WCR command is started by pulling the  $\overline{CS}$  pin low. The WCR opcode is then sent to the ENC28J60, followed by a 5-bit address (A4 through A0). The 5-bit address identifies any of the 32 control registers in the current bank. After the WCR command and address are sent, actual data that is to be written is sent, MSb first. The data will be written to the addressed register on the rising edge of the SCK line.

The WCR operation is terminated by raising the  $\overline{CS}$  pin. If the  $\overline{CS}$  line is allowed to go high before eight bits are loaded, the write will be aborted for that data byte. Refer to the timing diagram in Figure 4-5 for a more detailed illustration of the byte write sequence.



#### FIGURE 4-5: WRITE CONTROL REGISTER COMMAND SEQUENCE

#### 4.2.4 WRITE BUFFER MEMORY COMMAND

The Write Buffer Memory (WBM) command allows the host controller to write bytes to the integrated 8-Kbyte transmit and receive buffer memory.

If the AUTOINC bit in the ECON2 register is set, after the last bit of each byte is written, the EWRPT pointer will automatically be incremented to point to the next sequential address (current address + 1). If address 1FFFh is written with AUTOINC set, the write pointer will increment to 0000h.

The WBM command is started by lowering the  $\overline{CS}$  pin. The WBM opcode should then be sent to the ENC28J60, followed by the 5-bit constant 1Ah. After the WBM command and constant are sent, the data to be stored in the memory pointed to by EWRPT should be shifted out MSb first to the ENC28J60. After 8 data bits are received, the write pointer will automatically increment if AUTOINC is set. The host controller can continue to provide clocks on the SCK pin and send data on the SI pin, without raising  $\overline{CS}$ , to keep writing to the memory. In this manner, with AUTOINC enabled, it is possible to continuously write sequential bytes to the buffer memory without any extra SPI command overhead.

The WBM command is terminated by bringing up the  $\overline{\text{CS}}$  pin. Refer to Figure 4-6 for a detailed illustration of the write sequence.

#### 4.2.5 BIT FIELD SET COMMAND

The Bit Field Set (BFS) command is used to set up to 8 bits in any of the ETH Control registers. Note that this command cannot be used on the MAC registers, MII registers, PHY registers or buffer memory. The BFS command uses the provided data byte to perform a bit-wise OR operation on the addressed register contents.

The BFS command is started by pulling the  $\overline{CS}$  pin low. The BFS opcode is then sent, followed by a 5-bit address (A4 through A0). The 5-bit address identifies any of the ETH registers in the current bank. After the BFS command and address are sent, the data byte containing the bit field set information should be sent, MSb first. The supplied data will be logically ORed to the content of the addressed register on the rising edge of the SCK line for the D0 bit.


If the  $\overline{CS}$  line is brought high before eight bits are loaded, the operation will be aborted for that data byte. The BFS operation is terminated by raising the  $\overline{CS}$  pin.

#### 4.2.6 BIT FIELD CLEAR COMMAND

The Bit Field Clear (BFC) command is used to clear up to 8 bits in any of the ETH Control registers. Note that this command cannot be used on the MAC registers, MII registers, PHY registers or buffer memory. The BFC command uses the provided data byte to perform a bitwise NOTAND operation on the addressed register contents. As an example, if a register had the contents of F1h and the BFC command was executed with an operand of 17h, then the register would be changed to have the contents of E0h.

The BFC command is started by lowering the  $\overline{CS}$  pin. The BFC opcode should then be sent, followed by a 5-bit address (A4 through A0). The 5-bit address identifies any of the ETH registers in the current bank. After the BFC command and address are sent, a data byte containing the bit field clear information should be sent, MSb first. The supplied data will be logically inverted and subsequently ANDed to the contents of the addressed register on the rising edge of the SCK line for the D0 bit.

The BFC operation is terminated by bringing the  $\overline{CS}$  pin high. If  $\overline{CS}$  is brought high before eight bits are loaded, the operation will be aborted for that data byte.



#### FIGURE 4-6: WRITE BUFFER MEMORY COMMAND SEQUENCE

#### 4.2.7 SYSTEM COMMAND

The System Command (SC) allows the host controller to issue a System Soft Reset command. Unlike other SPI commands, the SC is only a single-byte command and does not operate on any register. The SC is started by pulling the  $\overline{\text{CS}}$  pin low. The SC opcode should then be sent, followed by a 5-bit Soft Reset command constant of 1Fh. The SC operation is terminated by raising the  $\overline{\text{CS}}$  pin. Figure 4-7 shows a detailed illustration of the System Command sequence.

For more information on SC's Soft Reset, refer to Section 11.2 "System Reset".




FIGURE 4-7: SYSTEM COMMAND SEQUENCE

### 5.0 ETHERNET OVERVIEW

Before discussing the use of the ENC28J60 as an Ethernet interface, it may be helpful to review the structure of a typical data frame. Users requiring more information should refer to IEEE Standard 802.3 which is the basis for the Ethernet protocol.

#### 5.1 Packet Format

Normal IEEE 802.3 compliant Ethernet frames are between 64 and 1518 bytes long. They are made up of five or six different fields: a destination MAC address, a source MAC address, a type/length field, data payload, an optional padding field and a Cyclic Redundancy Check (CRC). Additionally, when transmitted on the Ethernet medium, a 7-byte preamble field and start-offrame delimiter byte are appended to the beginning of the Ethernet packet. Thus, traffic seen on the twisted pair cabling will appear as shown in Figure 5-1.

## 5.1.1 PREAMBLE/START-OF-FRAME DELIMITER

When transmitting and receiving data with the ENC28J60, the preamble and start of frame delimiter bytes will automatically be generated or stripped from the packets when they are transmitted or received. The host controller does not need to concern itself with them. Normally, the host controller will also not need to concern itself with padding and the CRC which the ENC28J60 will also be able to automatically generate when transmitting and verify when receiving. The padding and CRC fields will, however, be written into the receive buffer when packets arrive, so they may be evaluated by the host controller if needed.




FIGURE 5-1: ETHERNET PACKET FORMAT

#### 5.1.2 DESTINATION ADDRESS

The destination address field is a 6-byte field filled with the MAC address of the device that the packet is directed to. If the Least Significant bit in the first byte of the MAC address is set, the address is a multicast destination. For example, 01-00-00-F0-00 and 33-45-67-89-AB-CD are multicast addresses, while 00-00-00-00-F0-00 and 32-45-67-89-AB-CD are not.

Packets with multicast destination addresses are designed to arrive and be important to a selected group of Ethernet nodes. If the destination address field is the reserved multicast address, FF-FF-FF-FF-FF, the packet is a broadcast packet and it will be directed to everyone sharing the network. If the Least Significant bit in the first byte of the MAC address is clear, the address is a unicast address and will be designed for usage by only the addressed node.

The ENC28J60 incorporates receive filters which can be used to discard or accept packets with multicast, broadcast and/or unicast destination addresses. When transmitting packets, the host controller is responsible for writing the desired destination address into the transmit buffer.

#### 5.1.3 SOURCE ADDRESS

The source address field is a 6-byte field filled with the MAC address of the node which created the Ethernet packet. Users of the ENC28J60 must generate a unique MAC address for each controller used.

MAC addresses consist of two portions. The first three bytes are known as the Organizationally Unique Identifier (OUI). OUIs are distributed by the IEEE. The last three bytes are address bytes at the discretion of the company that purchased the OUI.

When transmitting packets, the assigned source MAC address must be written into the transmit buffer by the host controller. The ENC28J60 will not automatically transmit the contents of the MAADR registers which are used for the unicast receive filter and unicast WOL filter.

#### 5.1.4 TYPE/LENGTH

The type/length field is a 2-byte field which defines which protocol the following packet data belongs to. Alternately, if the field is filled with the contents of 05DCh (1500) or any smaller number, the field is considered a length field and it specifies the amount of non-padding data which follows in the data field. Users implementing proprietary networks may choose to treat this field as a length field, while applications implementing protocols such as the Internet Protocol (IP) or Address Resolution Protocol (ARP), should program this field with the appropriate type defined by the protocol's specification when transmitting packets.

#### 5.1.5 DATA

The data field is a variable length field anywhere from 0 to 1500 bytes. Larger data packets will violate Ethernet standards and will be dropped by most Ethernet nodes. The ENC28J60, however, is capable of transmitting and receiving larger packets when the Huge Frame Enable bit is set (MACON3.HFRMEN = 1).

#### 5.1.6 PADDING

The padding field is a variable length field added to meet IEEE 802.3 specification requirements when small data payloads are used. The destination, source, type, data and padding of an Ethernet packet must be no smaller than 60 bytes. Adding the required 4-byte CRC field, packets must be no smaller than 64 bytes. If the data field is less than 46 bytes long, a padding field is required.

When transmitting packets, the ENC28J60 automatically generates zero padding if the MACON3.PADCFG<2:0> bits are configured to do so. Otherwise, the host controller should manually add padding to the packet before transmitting it. The ENC28J60 will not prevent the transmission of undersize packets should the host controller command such an action.

When receiving packets, the ENC28J60 automatically rejects packets which are less than 18 bytes. All packets 18 bytes and larger will be subject to the standard receive filtering criteria and may be accepted as normal traffic.

#### 5.1.7 CRC

The CRC field is a 4-byte field which contains an industry standard 32-bit CRC calculated with the data from the destination, source, type, data and padding fields.

When receiving packets, the ENC28J60 will check the CRC of each incoming packet. If ERXFCON.CRCEN is set, packets with invalid CRCs will automatically be discarded. If CRCEN is clear and the packet meets all other receive filtering criteria, the packet will be written into the receive buffer and the host controller will be able to determine if the CRC was valid by reading the receive status vector (see Section 7.2 "Receiving Packets").

When transmitting packets, the ENC28J60 will automatically generate a valid CRC and transmit it if the MACON3.PADCFG<2:0> bits are configured to cause this. Otherwise, the host controller must generate the CRC and place it in the transmit buffer. Given the complexity of calculating a CRC, it is highly recommended that the PADCFG bits be configured such that the ENC28J60 will automatically generate the CRC field.

### 6.0 INITIALIZATION

Before the ENC28J60 can be used to transmit and receive packets, certain device settings must be initialized. Depending on the application, some configuration options may need to be changed. Normally, these tasks may be accomplished once after Reset and do not need to be changed thereafter.

#### 6.1 Receive Buffer

Before receiving any packets, the receive buffer must be initialized by programming the ERXST and ERXND pointers. All memory between and including the ERXST and ERXND addresses will be dedicated to the receive hardware. It is recommended that the ERXST pointer be programmed with an even address.

Applications expecting large amounts of data and frequent packet delivery may wish to allocate most of the memory as the receive buffer. Applications that may need to save older packets or have several packets ready for transmission should allocate less memory.

When programming the ERXST pointer, the ERXWRPT registers will automatically be updated with the same values. The address in ERXWRPT will be used as the starting location when the receive hardware begins writing received data. For tracking purposes, the ERXRDPT registers should additionally be programmed with the same value. To program ERXRDPT, the host controller must write to ERXRDPTL first, followed by ERXRDPTH. See **Section 7.2.4 "Freeing Receive Buffer Space"** for more information.

#### 6.2 Transmission Buffer

All memory which is not used by the receive buffer is considered the transmission buffer. Data which is to be transmitted should be written into any unused space. After a packet is transmitted, however, the hardware will write a seven-byte status vector into memory after the last byte in the packet. Therefore, the host controller should leave at least seven bytes between each packet and the beginning of the receive buffer. No explicit action is required to initialize the transmission buffer.

#### 6.3 Receive Filters

The appropriate receive filters should be enabled or disabled by writing to the ERXFCON register. See **Section 8.0 "Receive Filters"** for information on how to configure it.

#### 6.4 Waiting For OST

If the initialization procedure is being executed immediately following a Power-on Reset, the ESTAT.CLKRDY bit should be polled to make certain that enough time has elapsed before proceeding to modify the MAC and PHY registers. For more information on the OST, see **Section 2.2 "Oscillator Start-up Timer"**.

#### 6.5 MAC Initialization Settings

Several of the MAC registers require configuration during initialization. This only needs to be done once; the order of programming is unimportant.

- 1. Clear the MARST bit in MACON2 to pull the MAC out of Reset.
- Set the MARXEN bit in MACON1 to enable the 2 MAC to receive frames. If using full duplex, most applications should also set TXPAUS and RXPAUS to allow IEEE defined flow control to function.
- 3 Configure the PADCFG, TXCRCEN and FULDPX bits of MACON3. Most applications should enable automatic padding to at least 60 bytes and always append a valid CRC. For convenience, many applications may wish to set the FRMLNEN bit as well to enable frame length status reporting. The FULDPX bit should be set if the application will be connected to a full-duplex configured remote node; otherwise, it should be left clear.
- 4. Configure the bits in MACON4. Many applications may not need to modify the Reset default.

MACON1: MAC CONTROL REGISTER 1

- 5. Program the MAMXFL registers with the maximum frame length to be permitted to be received or transmitted. Normal network nodes are designed to handle packets that are 1518 bytes or less.
- Configure the Back-to-Back Inter-Packet Gap 6. register, MABBIPG. Most applications will program this register with 15h when Full-Duplex mode is used and 12h when Half-Duplex mode is used.
- 7. Configure the Non-Back-to-Back Inter-Packet Gap register low byte, MAIPGL. Most applications will program this register with 12h.
- If half duplex is used, the Non-Back-to-Back 8. Inter-Packet Gap register high byte, MAIPGH, should be programmed. Most applications will program this register to 0Ch.
- 9. If Half-Duplex mode is used, program the Retransmission and Collision Window registers, MACLCON1 and MACLCON2. Most applications will not need to change the default Reset values. If the network is spread over exceptionally long cables, the default value of MACLCON2 may need to be increased.
- 10. Program the local MAC address into the MAADR0:MAADR5 registers.

REGISTER 6-1:	MACON1: MA	C CON	ITROL RE	GISTER 1								
	U-0 I	J-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0				
	—	—	—	LOOPBK	TXPAUS	RXPAUS	PASSALL	MARXEN				
	bit 7							bit 0				
bit 7-5	Unimplemente	d: Read	<b>as</b> '0'									
bit 4	LOOPBK: MAC	Loopb	ack Enable I	bit								
	1 = All data trar 0 = Normal ope		by the MA	C will be loop	ped back to	the MAC						
bit 3	TXPAUS: Pause	e Contro	ol Frame Tra	ansmission E	Enable bit							
	<ul><li>1 = Allow the M</li><li>0 = Disallow pa</li></ul>				ames (need	ed for flow c	ontrol in full	duplex)				
bit 2	RXPAUS: Paus	e Contr	ol Frame Re	eception Ena	able bit							
	<ul> <li>1 = Inhibit transmissions when pause control frames are received (normal operation)</li> <li>0 = Ignore pause control frames which are received</li> </ul>											
bit 1	PASSALL: Pass All Received Frames Enable bit											
	<ul> <li>1 = Control frames received by the MAC will be wirtten into the receive buffer if not filtered out</li> <li>0 = Control frames will be discarded after being processed by the MAC (normal operation)</li> </ul>											
bit 0	MARXEN: MAC Receive Enable bit											
	1 = Enable pac 0 = Disable pac			by the MAC								
	Logondi											
	Legend:	: <b>1</b>	10/ 10/				hit waard oo (	0'				
	R = Readable b			ritable bit		•	bit, read as '					
	-n – Value at PC	i R	'1' – Ri		(1) - Rit is	norcon :	v – Ritie u	nknown				

	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	
	PADCFG2	PADCFG1	PADCFG0	TXCRCEN	PHDRLEN	HFRMEN	FRMLNEN	FULDPX	
	bit 7	1	11			I	<b>- - -</b>	bit 0	
bit 7-5	PADCFG2	PACDFG0:	Automatic F	ad and CR	C Configura	tion bits			
					4 bytes and	a valid CR	C will then be	appended	
			adding of sho		and frames	which have	a 9100h tura	field and	
							a 8100h type t will be padd		
			adding, a va						
			adding of sho						
					4 bytes and	a valid CR	C will then be	appended	
			adding of sho will be zero i		0 hytes and	a valid CR(	C will then be	annended	
			adding of sho		o bytes and			appended	
bit 4		-	RC Enable I						
	1 = MAC will apend a valid CRC to all frames transmitted regardless of PADCFG. TXCRCEN								
	must be set if PADCFG specifies that a valid CRC will be appended.								
	0 = MAC will not append a CRC. The last 4 bytes will be checked and if it is an invalid CRC, it will be reported in the transmit status vector.								
bit 3	will be reported in the transmit status vector.								
DIL 3	PHDRLEN: Proprietary Header Enable bit								
	1 = Frames presented to the MAC contain a 4-byte proprietary header which will not be used when calculating the CRC								
	<ul> <li>0 = No proprietary header is present. The CRC will cover all data (normal operation).</li> </ul>								
bit 2	HFRMEN: Huge Frame Enable bit								
	1 = Frames of any size will be allowed to be transmitted and receieved								
	0 = Frames bigger than MAMXFL will be aborted when transmitted or received								
bit 1	FRMLNEN: Frame Length Checking Enable bit								
	1 = The type/length field of transmitted and received frames will be checked. If it represents a length, the frame size will be compared and mismatches will be reported in the transmit/receive status vector.								
	0 = Frame	e lengths will	not be comp	pared with th	ne type/leng	th field			
bit 0	FULDPX:	MAC Full-Du	uplex Enable	bit					
			n full-duplex. n half-duple>						
	Legend:								
	R – Reada	hle hit	M = M	ritable bit	II – Unim	nlemented	hit read as '	n'	

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented I	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

# **ENC28J60**

REGISTER 6-3:	MACON4	MAC CO		EGISTER 4						
	U-0	R/W-0	R/W-0	R/W-0	U-0	U-0	R/W-0	R/W-0		
	_	DEFER	BPEN	NOBKOFF	_	—	LONGPRE	PUREPRE		
	bit 7							bit 0		
bit 7	-	nented: Rea								
bit 6				ble bit (applie	•	• ·				
		the medium pting to trans		ed, the MAC v	will wait inde	efinately fo	r it to becom	e free when		
	0 = When		n is occupi	ed, the MAC 287 ms)	will abort th	ne transmis	ssion after th	e excessive		
bit 5	BPEN: No	Backoff Du	ring Back F	Pressure Enab	ole bit (appli	es to half c	luplex only)			
	<ul> <li>1 = After incidentally causing a collission during back pressure, the MAC will immediately begin retransmitting</li> <li>0 = After incidentally causing a collision during back pressure, the MAC will delay using the binary exponential backoff algorithm before attempting to retransmit (normal operation)</li> </ul>							ay using the		
bit 4										
	<ul> <li>NOBKOFF: No Backoff Enable bit (applies to half duplex only)</li> <li>1 = After any collision, the MAC will immediately begin retransmitting</li> <li>0 = After any collision, the MAC will delay using the binary exponential backoff algorithm before attempting to retransmit (normal operation)</li> </ul>						off algorithm			
bit 3-2	Unimplem	nented: Rea	<b>d as</b> '0'							
bit 1	LONGPRE: Long Preamble Enforcement Enable bit									
	<ul> <li>1 = Received packets will be rejected if they are preceded by 12 or more bytes of preamble</li> <li>0 = Received packets will not be rejected if they have 12 or more bytes of preamble (normal operation)</li> </ul>									
bit 0	PUREPRE	: Pure Prea	mble Enfor	cement Enab	le bit					
	1 = The preamble of received packets will be checked against 55h. If it contains an error, the packet will be discarded.									
	0 = The p	reamble of r	eceived pa	ckets will not	be checked					
	· ·							]		
	Legend:									

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

#### REGISTER 6-4: MABBIPG: MAC BACK-TO-BACK INTER-PACKET GAP REGISTER

	U-0	R/W-0						
	_	BBIPG6	BBIPG5	BBIPG4	BBIPG3	BBIPG2	BBIPG1	BBIPG0
bit	: 7							bit 0

bit 7 Unimplemented: Read as '0'

#### bit 6-0 BBIPG6:BBIPG0: Back-to-Back Inter-Packet Gap Delay Time bits

#### When MACON3.FULDPX = 1:

Nibble time offset delay between the end of one transmission and the beginning of the next in a back-to-back sequence. The register value should be programmed to the desired period in nibble times minus 3. The recommended setting is 15h which represents the minimum IEEE specified Inter-Packet Gap (IPG) of 9.6  $\mu$ s.

#### When MACON3.FULDPX = 0:

Nibble time offset delay between the end of one transmission and the beginning of the next in a back-to-back sequence. The register value should be programmed to the desired period in nibble times minus 6. The recommended setting is 12h which represents the minimum IEEE specified Inter-Packet Gap (IPG) of 9.6  $\mu$ s.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

# 6.6 PHY Initialization Settings

Depending on the application, bits in three of the PHY module's registers may also require configuration.

The PHCON1.PDPXMD bit partially controls the device's half/full-duplex configuration. Normally, this bit is initialized correctly by the external circuitry (see **Section 2.6 "LED Configuration**"). If the external circuitry is not present or incorrect, however, the host controller must program the bit properly. Alternatively, for an externally configurable system, the PDPXMD bit may be read and the FULDPX bit be programmed to match.

For proper duplex operation, the PHCON1.PDPXMD bit must also match the value of the MACON3.FULDPX bit.

If using half duplex, the host controller may wish to set the PHCON2.HDLDIS bit to prevent automatic loopback of the data which is transmitted.

The PHY register, PHLCON, controls the outputs of LEDA and LEDB. If an application requires a LED configuration other than the default, PHLCON must be altered to match the new requirements. The settings for LED operation are discussed in **Section 2.6** "LED **Configuration**". The PHLCON register is shown in Register 2-2 (page 9).

U-0	R/W-0	R/W-0	R/W-x	R/W-x	R/W-0	R/W-0	R/W-0			
_	FRCLNK	TXDIS	r	r	JABBER	r	HDLDIS			
oit 15										
	R/W-x	R/W->	k R/W->	k R/W-	x R/W-x	R/W-x	R/W-x	R/W-x		
	r	r	r	r	r	r	r	r		
	bit 7							bit		
oit 15	Unimplemente	d: Read as '	0'							
oit 14	FRCLNK: PHY	Force Linku	p bit							
	1 = Force linku 0 = Normal ope		n no link parti	ner is detect	ed					
oit 13	TXDIS: Twisted	Pair Transn	nitter Disable	bit						
	1 = Disable twi		nsmitter							
	0 = Normal ope									
	Reserved: Writ									
bit 10	JABBER: Jabb									
	<ul><li>1 = Disable jab</li><li>0 = Normal ope</li></ul>		on							
bit 9	Reserved: Writ	e as '0'								
bit 8	HDLDIS: PHY H	Half-Duplex	Loopback Dis	sable bit						
	When PHCON1	.PDPXMD =	1 or PHCO	N1.PLOOPE	<u> 8K = 1:</u>					
	This bit is ignore	ed.								
	When PHCON1.PDPXMD = 0 and PHCON1.PLOOPBK = 0:									
	1 = Transmittee 0 = Transmittee		•		•		pair interface			

# REGISTER 6-5: PHCON2: PHY CONTROL REGISTER 2

Legend:	r = Reserved bit		
R = Readable bit	W = Writable bit	U = Unimplemented bit, re	ead as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown


# 7.0 TRANSMITTING AND RECEIVING PACKETS


#### 7.1 Transmitting Packets

The MAC inside the ENC28J60 will automatically generate the preamble and start-of-frame delimiter fields when transmitting. Additionally, the MAC can generate any padding (if needed) and the CRC if configured to do so. The host controller must generate and write all other frame fields into the buffer memory for transmission. Additionally, the ENC28J60 requires a single per packet control byte to precede the packet for transmission. The per packet control byte is organized as shown in Figure 7-1. Before transmitting packets, the MAC registers which alter the transmission characteristics should be initialized as documented in **Section 6.0** "**Initialization**".

For an example of how the entire transmit packet and results will look in memory, see Figure 7-2.

#### FIGURE 7-1: FORMAT FOR PER PACKET CONTROL BYTES





#### FIGURE 7-2: SAMPLE TRANSMIT PACKET LAYOUT

To achieve the example layout shown in Figure 7-2 and to transmit a packet, the host controller should:

- 1. Appropriately program the ETXST pointer to point to an unused location in memory. It will point to the per packet control byte. In the example, it would be programmed to 0120h. It is recommended that an even address be used for ETXST.
- 2. Use the WBM SPI command to write the per packet control byte, the destination address, the source MAC address, the type/length and the data payload.
- Appropriately program the ETXND pointer. It should point to the last byte in the data payload. In the example, it would be programmed to 0156h.
- 4. Clear EIR.TXIF, set EIE.TXIE and set EIE.INTIE to enable an interrupt when done (if desired).
- 5. Start the transmission process by setting ECON1.TXRTS.

If a DMA operation was in progress while the TXRTS bit was set, the ENC28J60 will wait until the DMA operation is complete before attempting to transmit the packet. This possible delay is required because the DMA and transmission engine share the same memory access port. Similarly, if the DMAST bit in ECON1 is set after TXRTS is already set, the DMA will wait until the TXRTS bit becomes clear before doing anything. While the transmission is in progress, none of the unshaded bits (except for the EECON1 register's bits) in Table 7-2 should be changed. Additionally, none of the bytes to be transmitted should be read or written to through the SPI. If the host controller wishes to cancel the transmission, it can clear the TXRTS bit.

When the packet is finished transmitting or was aborted due to an error/cancellation, the ECON1.TXRTS bit will be cleared, a seven-byte transmit status vector will be written to the location pointed to by ETXND + 1, the EIR.TXIF will be set and an interrupt will be generated (if enabled). The ETXST and ETXND pointers will not be modified. To check if the packet was successfully transmitted, the ESTAT.TXABRT bit should be read. If it was set, the host controller may interrogate the ESTAT.LATECOL bit in addition to the various fields in the transmit status vector to determine the cause. The transmit status vector is organized as shown in Table 7-1. Multi-byte fields are written in little-endian format.

Bit	Field	Description
63-52	Zero	0
51	Transmit VLAN Tagged Frame	Frame's length/type field contained 8100h which is the VLAN protocol identifier.
50	Backpressure Applied	Carrier sense method backpressure was previously applied.
49	Transmit Pause Control Frame	The frame transmitted was a control frame with a valid pause opcode.
48	Transmit Control Frame	The frame transmitted was a control frame.
47-32	Total Bytes Transmitted on Wire	Total bytes transmitted on the wire for the current packet, including all bytes from collided attempts.
31	Transmit Underrun	Reserved. This bit will always be '0'.
30	Transmit Giant	Byte count for frame was greater than MAMXFL.
29	Transmit Late Collision	Collision occurred beyond the collision window (MACLCON2).
28	Transmit Excessive Collision	Packet was aborted after the number of collisions exceeded the retransmission maximum (MACLCON1).
27	Transmit Excessive Defer	Packet was deferred in excess of 24,287 bit times (2.4287ms).
26	Transmit Packet Defer	Packet was deferred for at least one attempt but less than an excessive defer.
25	Transmit Broadcast	Packet's destination address was a broadcast address.
24	Transmit Multicast	Packet's destination address was a multicast address.
23	Transmit Done	Transmission of the packet was completed.
22	Transmit Length Out of Range	Indicates that frame type/length field was larger than 1500 bytes (type field).
21	Transmit Length Check Error	Indicates that frame length field value in the packet does not match the actual data byte length and is not a type field. MACON3.FRMLNEN must be set to get this error.
20	Transmit CRC Error	The attached CRC in the packet did not match the internally generated CRC.
19-16	Transmit Collision Count	Number of collisions the current packet incurred during transmission attempts. It applies to successfully transmitted packets and as such, will not show the possible maximum count of 16 collisions.
15-0	Transmit Byte Count	Total bytes in frame not counting collided bytes.

TABLE 7-1: TRANSMIT STATUS VECTORS

Register Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on page
EIE	INTIE	PKTIE	DMAIE	LINKIE	TXIE	WOLIE	TXERIE	RXERIE	13
EIR	_	PKTIF	DMAIF	LINKIF	TXIF	WOLIF	TXERIF	RXERIF	13
ESTAT	INT	r	r	LATECOL	—	RXBUSY	TXABRT	CLKRDY	13
ECON1	TXRST	RXRST	DMAST	CSUMEN	TXRTS	RXEN	BSEL1	BSEL0	13
ETXSTL	TX Start Low	v Byte (ETXS	T<7:0>)						13
ETXSTH	_	_	_	TX Start Hig	h Byte (ETXS	T<12:8>)			13
ETXNDL	TX End Low	Byte (ETXNI	D<7:0>)						13
ETXNDH	_	_	_	TX End High	n Byte (ETXN	D<12:8>)			13
MACON1	_	_	_	LOOPBK	TXPAUS	RXPAUS	PASSALL	MARXEN	14
MACON2	MARST	RNDRST	_	_	MARXRST	RFUNRST	MATXRST	TFUNRST	14
MACON3	PADCFG2	PADCFG1	PADCFG0	TXCRCEN	PHDRLEN	HFRMEN	FRMLNEN	FULDPX	14
MACON4	_	DEFER	BPEN	NOBKOFF	_		LONGPRE	PUREPRE	14
MABBIPG	—	Back-to-Bac	k Inter-Packe	t Gap (BBIPC	6<6:0>)				14
MAIPGL	_	Non-Back-to	-Back Inter-P	acket Gap Lo	ow Byte (MAIF	PGL<6:0>)			14
MAIPGH	_	Non-Back-to	-Back Inter-P	acket Gap Hi	gh Byte (MAI	PGH<6:0>)			14
MACLCON1	_	_	_	_	Retransmiss	ion Maximum	n (RETMAX<3	3:0>)	14
MACLCON2	_	_	Collision Wir	ndow (COLW	IN<5:0>)				14
MAMXFLL	Maximum Fr	ame Length I	Low Byte (MA	MXFL<7:0>)					14
MAMXFLH	Maximum Fr	ame Length I	High Byte (M/	AMXFL<15:8	>)				14
MAPHSUP	r	_	_	r	RSTRMII	_	_	r	14

#### TABLE 7-2: SUMMARY OF REGISTERS USED FOR PACKET TRANSMISSION

**Legend:** — = unimplemented, r = reserved bit. Shaded cells are not used.

# 7.2 Receiving Packets

#### 7.2.1 ENABLING RECEPTION

Assuming that the receive buffer has been initialized, the MAC has been properly configured and the receive filters have been configured to receive Ethernet packets, the host controller should:

- 1. If an interrupt is desired whenever a packet is received, set EIE.PKTIE and EIE.INTIE.
- 2. If an interrupt is desired whenever a packet is dropped due to insufficient buffer space, clear EIR.RXERIF and set both EIE.RXERIE and EIE.INTIE
- 3. Enable reception by setting ECON1.RXEN.


After setting RXEN, the Duplex mode and the receive buffer start and end pointers should not be modified. Additionally, to prevent unexpected packets from arriving, it is recommended that RXEN be cleared before altering the receive filter configuration (ERXFCON) and MAC address. After reception is enabled, packets which are not filtered out will be written into the circular receive buffer. Any packet which does not meet the necessary filter criteria will be discarded and the host controller will not have any means of identifying that a packet was thrown away. When a packet is accepted and completely written into the buffer, the EPKTCNT register will increment, the EIR.PKTIF bit will be set, an interrupt will be generated (if enabled) and the hardware write pointer, ERXWRPT, will automatically advance.

#### 7.2.2 RECEIVE PACKET LAYOUT

Figure 7-3 shows the layout of a received packet. The packets are preceded by a six-byte header which contains a next packet pointer, in addition to a receive status vector which contains receive statistics, including the packet's size. This receive status vector is shown in Table 7-3.

If the last byte in the packet ends on an odd value address, the hardware will automatically add a padding byte when advancing the hardware write pointer. As such, all packets will start on an even boundary.





Bit	Field	Description
31	Zero	0
30	Receive VLAN Type Detected	Current frame was recognized as a VLAN tagged frame.
29	Receive Unknown Opcode	Current frame was recognized as a control frame but it contained an unknown opcode.
28	Receive Pause Control Frame	Current frame was recognized as a control frame containing a valid pause frame opcode and a valid destination address.
27	Receive Control Frame	Current frame was recognized as a control frame for having a valid type/length designating it as a control frame.
26	Dribble Nibble	Indicates that after the end of this packet, an additional 1 to 7 bits were received. The extra bits were thrown away.
25	Receive Broadcast Packet	Indicates packet received had a valid broadcast address.
24	Receive Multicast Packet	Indicates packet received had a valid multicast address.
23	Received Ok	Indicates that at the packet had a valid CRC and no symbol errors.
22	Length Out of Range	Indicates that frame type/length field was larger than 1500 bytes (type field).
21	Length Check Error	Indicates that frame length field value in the packet does not match the actual data byte length and specifies a valid length.
20	CRC Error	Indicates that frame CRC field value does not match the CRC calculated by the MAC.
19	Reserved	
18	Carrier Event Previously Seen	Indicates that at some time since the last receive, a carrier event was detected. The carrier event is not associated with this packet. A carrier event is activity on the receive channel that does not result in a packet receive attempt being made.
17	Reserved	
16	Long Event/Drop Event	Indicates a packet over 50,000 bit times occurred or that a packet was dropped since the last receive.
15-0	Received Byte Count	Indicates length of the received frame. This includes the destination address, source address, type/length, data, padding and CRC fields. This field is stored in little-endian format.

## TABLE 7-3: RECEIVE STATUS VECTOR

#### 7.2.3 READING RECEIVED PACKETS

To process the packet, the host controller will normally use the RBM SPI command and start reading from the beginning of the next packet pointer. The host controller will save the next packet pointer, any necessary bytes from the receive status vector and then proceed to read the actual packet contents. If ECON2.AUTOINC is set, it will be able to sequentially read the entire packet without ever modifying the ERDPT registers. The read pointer would automatically wrap at the end of the circular receive buffer to the beginning. In the event that the application needed to do random access to the packet, it would be necessary to manually calculate the proper ERDPT, taking care to not exceed the end of the receive buffer if the packet spans the ERXND-to-ERXST buffer boundary. In other words, given the packet start address and a desired offset, the application should follow the logic shown in Example 7-1.

#### EXAMPLE 7-1: RANDOM ACCESS ADDRESS CALCULATION

if Packet Start Address + Offset > ERXND, then

ERDPT = Packet Start Address + Offset - (ERXND - ERXST + 1)

else

 $ERDPT = Packet \ Start \ Address + Offset$ 

#### 7.2.4 FREEING RECEIVE BUFFER SPACE

After the host controller has processed a packet (or part of the packet) and wishes to free the buffer space used by the processed data, the host controller must advance the receive buffer read pointer, ERXRDPT. The ENC28J60 will always write up to, but not including, the memory pointed to by the receive buffer read pointer. If the ENC28J60 ever attempts to overwrite the receive buffer read pointer location, the packet in progress will be aborted, the EIR.RXERIF will be set and an interrupt will be generated (if enabled). In this manner, the hardware will never overwrite unprocessed packets. Normally, the ERXRDPT will be advanced to the value pointed to by the next packet pointer which precedes the receive status vector for the current packet. Following such a procedure will not require any pointer calculations to account for wrapping at the end of the circular receive buffer.

The receive buffer read pointer low byte (ERXRDPTL register) is internally buffered to prevent the pointer from moving when only one byte is updated through the SPI. To move ERXRDPT, the host controller must write to ERXRDPTL first. The write will update the internal buffer but will not affect the register. When the host controller writes to ERXRDPTH, the internally buffered low byte will be loaded into the ERXRDPTL register at the same time. The ERXRDPT bytes can be read in any order. When they are read, the actual value of the registers will be returned. As a result, the buffered low byte is not readable.

In addition to advancing the receive buffer read pointer, after each packet is fully processed, the host controller must write a '1' to the ECON2.PKTDEC bit. Doing so will cause the EPKTCNT register to decrement by 1. After decrementing, if EPKTCNT is '0', the EIR.PKTIF flag will automatically be cleared. Otherwise, it will remain set, indicating that additional packets are in the receive buffer and are waiting to be processed. Attempts to decrement EPKTCNT below 0 are ignored. Additionally, if the EPKTCNT register ever maximizes at 255, all new packets which are received will be aborted, even if buffer space is available. To indicate the error, the EIR.RXERIF will be set and an interrupt will be generated (if enabled). To prevent this condition, the host controller must properly decrement the counter whenever a packet is processed.

Because only one pointer is available to control buffer area ownership, the host controller must process packets in the order they are received. If the host controller wishes to save a packet to be processed later, it should copy the packet to an unused location in memory. It may accomplish this efficiently using the integrated DMA controller (see Section 13.0 "Direct Memory Access Controller").

#### 7.2.5 RECEIVE BUFFER FREE SPACE

At any time the host controller wishes to know how much receive buffer space is remaining, it should read the hardware write pointer (ERXWRPT registers) and compare it with the ERXRDPT registers. Combined with the known size of the receive buffer, the free space can be derived.

Note:	The ERXWRPT registers only update when a packet has been successfully
	received. If the host controller reads it just
	before another packet is to be successfully
	completed, the value returned could be
	stale and off by the maximum frame length
	permitted (MAMXFLN) plus 7. Further-
	more, as the host controller reads one
	byte of ERXWRPT, a new packet may
	arrive and update the pointer before the
	host controller has an opportunity to read
	the other byte of ERXWRPT.

When reading the ERXWRPT register with the receive hardware enabled, special care must be taken to ensure the low and high bytes are read as a matching set.

To be assured that a matching set is obtained:

- 1. Read the EPKTCNT register and save its contents.
- 2. Read ERXWRPTL and ERXWRPTH.
- 3. Read the EPKTCNT register again.
- 4. Compare the two packet counts. If they are not the same, go back to step 2.

With the hardware write pointer obtained, the free space can be calculated as shown in Example 7-2. The hardware prohibits moving the write pointer to the same value occupied by ERXRDPT (except when the buffer pointers are being configured), so at least one byte will always go unused in the buffer. The example calculation reflects the lost byte.

#### EXAMPLE 7-2: RECEIVE BUFFER FREE SPACE CALCULATION

if ERXWRPT > ERXRDPT, then

Free Space = (ERXND - ERXST) - (ERXWRPT - ERXRDPT)

else if ERXWRPT = ERXRDPT, then

Free Space = (ERXND - ERXST)

else

Free Space = ERXRDPT - ERXWRPT - 1

Register Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on page
EIE	INTIE	PKTIE	DMAIE	LINKIE	TXIE	WOLIE	TXERIE	RXERIE	13
EIR	_	PKTIF	DMAIF	LINKIF	TXIF	WOLIF	TXERIF	RXERIF	13
ESTAT	INT	r	r	LATECOL	_	RXBUSY	TXABRT	CLKRDY	13
ECON2	AUTOINC	PKTDEC	PWRSV	_	VRPS	_	_	—	13
ECON1	TXRST	RXRST	DMAST	CSUMEN	TXRTS	RXEN	BSEL1	BSEL0	13
ERXSTL	RX Start Lov	RX Start Low Byte (ERXST<7:0>)							13
ERXSTH	_	RX Start High Byte (ERXST<12:8>)							
ERXNDL	RX End Low	RX End Low Byte (ERXND<7:0>)							
ERXNDH	_	_	_	RX End High	n Byte (ERXN	D<12:8>)			13
ERXRDPTL	RX RD Point	ter Low Byte	ERXRDPT<7	':0>)					13
ERXRDPTH	_	_		RX RD Point	ter High Byte	(ERXRDPT<1	12:8>)		13
ERXFCON	UCEN	ANDOR	CRCEN	PMEN	MPEN	HTEN	MCEN	BCEN	14
EPKTCNT	Ethernet Pac	cket Count		•	•		•		14
MACON1	_	_	_	LOOPBK	TXPAUS	RXPAUS	PASSALL	MARXEN	14
MACON2	MARST	RNDRST		_	MARXRST	RFUNRST	MATXRST	TFUNRST	14
MACON3	PADCFG2	PADCFG1	PADCFG0	TXCRCEN	PHDRLEN	HFRMEN	FRMLNEN	FULDPX	14
MACON4	_	DEFER	BPEN	NOBKOFF	_	_	LONGPRE	PUREPRE	14
MAMXFLL	Maximum Fr	ame Length I	ow Byte (MA	MXFL<7:0>)					14
MAMXFLH	Maximum Frame Length High Byte (MAMXFL<15:8>)								14
MAPHSUP	r	—	_	r	RSTRMII	—	—	r	14

# TABLE 7-4: SUMMARY OF REGISTERS USED FOR PACKET RECEPTION

**Legend:** — = unimplemented, r = reserved bit. Shaded cells are not used.

# 8.0 RECEIVE FILTERS

To minimize the processing requirements of the host controller, the ENC28J60 incorporates several different receive filters which can automatically reject packets which are not needed. Six different types of packet filters are implemented:


- Unicast
- Pattern Match
- Magic Packet<sup>™</sup>
- Hash Table
- Multicast
- Broadcast

The individual filters are all configured by the ERXFCON register (Register 8-1). More than one filter can be active at any given time. Additionally, the filters can be configured by the ANDOR bit to either logically AND, or logically OR, the tests of several filters. In other words, the filters may be set so that only packets accepted by all active filters are accepted, or a packet accepted by any one filter is accepted. The flowcharts in Figure 8-1 and Figure 8-2 show the effect that each of the filters will have depending on the setting of ANDOR.

The device can enter Promiscuous mode and receive all packets by clearing the ERXFCON register. The proper setting of the register will depend on the application requirements.


REGISTER 8-1:	ERXFCO	N: RECEIV		CONTROL	REGISTE	R						
	R/W-1	R/W-0	R/W-1	R/W-0	R/W-0	R/W-0	R/W-0	R/W-1				
	UCEN	ANDOR	CRCEN	PMEN	MPEN	HTEN	MCEN	BCEN				
	bit 7							bit 0				
bit 7	When AND	s not having		address m	atching the I	ocal MAC a	ddress will b	e discarded				
	When AND 1 = Packets 0 = Filter d	s with a dest	ination addre	ess matchin	g the local N	IAC addres	s will be acc	epted				
bit 6	1 = AND: F	<ul> <li>NDOR: AND/OR Filter Select bit</li> <li>AND: Packets will be rejected unless all enabled filters accept the packet</li> <li>OR: Packets will be accepted unless all enabled filters reject the packet</li> </ul>										
bit 5	1 = All pac	RCEN: Post-Filter CRC Check Enable bit = All packets with an invalid CRC will be discarded = The CRC validity will be ignored										
bit 4	When AND 1 = Packets 0 = Filter d When AND	<b>MEN:</b> Pattern Match Filter Enable bit <u>hen ANDOR = 1:</u> = Packets must meet the pattern match criteria or they will be discarded = Filter disabled <u>hen ANDOR = 0:</u> = Packets which meet the pattern match criteria will be accepted										
bit 3	When AND 1 = Packets 0 = Filter d When AND	s must be Ma isabled 9 <u>OR = 0:</u> Packets for tl	agic Packets	for the loca		-	will be disca	rded				
bit 2	When AND 1 = Packets 0 = Filter d When AND	s must meet isabled ) <u>OR = 0:</u> s which mee	the hash tab		·							
bit 1	MCEN: Mu When AND 1 = Packets 0 = Filter d When AND	Iticast Filter 1 OR = 1: must have the isabled OR = 0: s which have	ne Least Sign				-					
bit 0	BCEN: Bro When AND 1 = Packet 0 = Filter d When AND	padcast Filter OR = 1: s must have isabled OR = 0: s which have	a destinatior									
	Legend:	bla k :	147 147					-0 <sup>2</sup>				
	R = Reada			ritable bit		-	bit, read as '					
	- n = Value	aLFUK	'1' = Bi	115 561	U = BIUS	s cleared	x = Bit is u					





# **ENC28J60**





# 8.1 Unicast Filter

The unicast receive filter checks the destination address of all incoming packets. If the destination address exactly matches the contents of the MAADR registers, the packet will meet the unicast filter criteria.

# 8.2 Pattern Match Filter

The pattern match filter selects up to 64 bytes from the incoming packet and calculates an IP checksum of the bytes. The checksum is then compared to the EPMCS registers. The packet meets the pattern match filter criteria if the calculated checksum matches the EPMCS registers. The pattern match filter may be useful for filtering packets which have expected data inside them.


To use the pattern match filter, the host controller must program the pattern match offset (EPMOH:EPMOL), all of the pattern match mask bytes (EPMM7:EPMM0) and the pattern match checksum resister pair (EPMCSH:EPMCSL). The pattern match offset should be loaded with the offset from the beginning of the destination address field to the 64-byte window which will be used for the checksum computation. Within the 64-byte window, each individual byte can be selectively included or excluded from the checksum computation by setting or clearing the respective bit in the pattern match mask. If a packet is received which would cause the 64 byte window to extend past the end of the CRC,

the filter criteria will immediately not be met, even if the corresponding mask bits are all '0'. The pattern match checksum registers should be programmed to the checksum which is expected for the selected bytes. The checksum is calculated in the same manner that the DMA module calculates checksums (see **Section 13.2 "Checksum Calculations"**). Data bytes which have corresponding mask bits programmed to '0' are completely removed for purposes of calculating the checksum, as opposed to treating the data bytes as zero.

As an example, if the application wished to filter all packets having a particular source MAC address of 00-04-A3-FF-FF-FF, it could program the pattern match offset to 0000h and then set bits 6 and 7 of EPMM0 and bits 0, 1, 2 and 3 of EPMM1 (assuming all other mask bits are '0'). The proper checksum to program into the EPMCS registers would be 0x5BFC. As an alternative configuration, it could program the offset to 0006h and set bits 0, 1, 2, 3, 4 and 5 of EPMM0. The checksum would still be 5BFCh. However, the second case would be less desirable as packets less than 70 bytes long could never meet the pattern match criteria, even if they would generate the proper checksum given the mask configuration.

Another example of a pattern matching filter is illustrated in Figure 8-3.


# FIGURE 8-3: SAMPLE PATTERN MATCHING FORMAT



#### 8.3 Magic Packet<sup>™</sup> Filter

The Magic Packet filter checks the destination address and data fields of all incoming packets. If the destination address matches the MAADR registers and the data field holds a valid Magic Packet pattern someplace within it, then the packet will meet the Magic Packet filter criteria. The Magic Packet pattern consists of a sync pattern of six 0xFF bytes, followed by 16 repeats of the destination address. See Figure 8-4 for a sample Magic Packet.

FIGURE 8-4: SAMPLE MAGIC PACKET™



#### 8.4 Hash Table Filter

The hash table receive filter performs a CRC over the six destination address bytes in the packet. The CRC is then used as a pointer into the bits of the EHT registers. If the pointer points to a bit which is set, the packet meets the hash table filter criteria. For example, if the CRC is calculated to be 0x5, bit 5 in the hash table will be checked. If it is set, the hash table filter criteria will be met. If every bit is clear in the hash table, the filter criteria will never be met. Similarly, if every bit is set in the hash table, the filter criteria will always be met.

#### 8.5 Multicast Filter

The multicast receive filter checks the destination address of all incoming packets. If the Least Significant bit of the first byte of the destination address is set, the packet will meet the multicast filter criteria.

#### 8.6 Broadcast Filter

The broadcast receive filter checks the destination address of all incoming packets. If the destination address is FF-FF-FF-FF-FF-FF, the packet will meet the broadcast filter criteria.

# 9.0 DUPLEX MODE CONFIGURATION AND NEGOTIATION

The ENC28J60 does not support automatic duplex negotiation. If it is connected to an automatic duplex negotiation enabled network switch or Ethernet controller, the ENC28J60 will be detected as a half-duplex device. To communicate in Full-Duplex mode, the ENC28J60 and the remote node (switch, router or Ethernet controller) must be manually configured for full-duplex operation.

# 9.1 Half-Duplex Operation

The ENC28J60 operates in Half-Duplex mode when MACON3.FULDPX = 0 and PHCON1.PDPXMD = 0. If only one of these two bits is set, the ENC28J60 will be in an indeterminate state and not function correctly. Since switching between Full and Half-Duplex modes may result in this indeterminate state, the host controller should not transmit any packets (maintain ECON1.TXRTS clear) and packet reception should be disabled (ECON1.RXEN and ESTAT.RXBUSY should be clear) during this period.

In Half-Duplex mode, only one Ethernet controller may be transmitting on the physical medium at any time. If the host controller sets the ECON1.TXRTS bit, requesting that a packet be transmitted while another Ethernet controller is already transmitting, the ENC28J60 will delay, waiting for the remote transmitter to stop. After the transmission stops, the ENC28J60 will attempt to transmit its packet. If another Ethernet controller starts transmitting at approximately the same time that the ENC28J60 starts transmitting, the data on the wire will become corrupt and a collision will occur. The hardware will handle this condition in one of two ways:

1. If the collision occurs before the number of bytes specified by the "Collision Window" in MACLCON2 were transmitted. the ECON1.TXRTS bit will remain set, a random exponential back off delay will elapse as defined by the IEEE 802.3 specification and then a new attempt to transmit the packet from the beginning will occur. The host controller will not need to intervene. If the number of retransmission attempts already matches the "Retransmission Maximum" (RETMAX) defined in MACLCON1, the packet will be aborted and ECON1.TXRTS will be cleared. The host controller will then be responsible for taking appropriate action. The host controller will be able to determine that the packet was aborted instead of being successfully transmitted by reading the ESTAT.TXABRT flag. For more information, see Section 7.1 "Transmitting Packets". A transmit abort will cause the transmit error interrupt.

2. If the collision occurs after the number of bytes specified by the "Collision Window" in MACLCON2 were transmitted, the packet will be immediately aborted without any retransmission attempts. Ordinarily, in 802.3 compliant networks which are properly configured, this late collision will not occur. User intervention may be required to correct the issue. This problem may occur as a result of a full-duplex node attempting to transmit on the half-duplex medium. Alternately, the ENC28J60 may be attempting to operate in Half-Duplex mode while it may be connected to a full-duplex network. Excessively long cabling and network size may also be a possible cause of late collisions.

When set in Half-Duplex mode, the Reset default configuration will loop transmitted packets back to itself. Unless the receive filter configuration filters these packets out, they will be written into the circular receive buffer, just as any other network traffic. To stop this behavior, the host controller should set the PHCON2.HDLDIS bit.

# 9.2 Full-Duplex Operation

The ENC28J60 operates in Full-Duplex mode when MACON3.FULDPX = 1 and PHCON1.PDPXMD = 1. If only one of these two bits is clear, the ENC28J60 will be in an indeterminate state and not function correctly. Since switching between Full and Half-Duplex modes may result in this indeterminate state, the host controller should not transmit any packets (maintain ECON1.TXRTS clear) and packet reception should be disabled (ECON1.RXEN and ESTAT.RXBUSY should be clear) during this period.

In Full-Duplex mode, packets will be transmitted simultaneously while packets may be received. Given this, it is impossible to cause any collisions when transmitting packets. Several configuration fields, such as "Retransmission Maximum" (RETMAX) in MACLCON1 and "Collision Window" (COLWIN) in MACLCON2, will not be used.

When set in Full-Duplex mode, the Reset default configuration will not loop transmitted packets back to itself. If loopback is desired for diagnostic purposes, the PHCON1.PLOOPBK bit should be set by the host controller. Enabling loopback in Full-Duplex mode will disable the twisted pair output driver and ignore all incoming data, thus dropping any link (if established). All packets received as a result of the loopback configuration will be subject to all enabled receive filters, just as ordinary network traffic would be. NOTES:

# 10.0 FLOW CONTROL

The ENC28J60 implements hardware flow control for both Full and Half-Duplex modes. The operation of this feature differs depending on which mode is being used.

# 10.1 Half-Duplex Mode

In Half-Duplex mode, setting the EFLOCON.FCEN0 bit causes flow control to be enabled. When FCEN0 is set, a continuous preamble pattern of alternating '1's and '0's (55h) will automatically be transmitted on the Ethernet medium. Any connected nodes will see the transmission and either not transmit anything, waiting for the ENC28J60's transmission to end, or will attempt to transmit and immediately cause a collision. Because a collision will always occur, no nodes on the network will be able to communicate with each other and no new packets will arrive.

When the host controller tells the ENC28J60 to transmit a packet by setting ECON1.TXRTS, the preamble pattern will stop being transmitted. An Inter-Packet Gap delay will pass as configured by register MABBIPG and then the ENC28J60 will attempt to transmit its packet. During the Inter-Packet Gap delay, other nodes may begin to transmit. Because all traffic was jammed previously, several nodes may begin transmitting and a series of collisions may occur. When the ENC28J60 successfully finishes transmitting its packet or aborts it, the transmission of the preamble pattern will automatically restart. When the host controller wishes to no longer jam the network, it should clear the FCEN0 bit. The preamble transmission will cease and normal network operation will resume.

Given the detrimental network effects that are possible and lack of effectiveness, it is not recommend that halfduplex flow control be used unless the application will be in a closed network environment with proper testing.

# 10.2 Full-Duplex Mode

In Full-Duplex mode (MACON3.FULDPX = 1), hardware flow control is implemented by means of transmitting pause control frames as defined by the IEEE 802.3 specification. Pause control frames are 64-byte frames consisting of the reserved multicast destination address of 01-80-C2-00-00-01, the source address of the sender, a special pause opcode, a two-byte pause timer value and padding/CRC.


Normally, when a pause control frame is received by a MAC, the MAC will finish the packet it is transmitting and then stop transmitting any new frames. The pause timer value will be extracted from the control frame and used to initialize an internal timer. The timer will auto-

matically decrement every 512 bit times or 51.2  $\mu$ s. While the timer is counting down, reception of packets is still enabled. If new pause frames arrive, the timer will be reinitialized with the new pause timer value. When the timer reaches zero or was sent a frame with a zero pause timer value, the MAC that received the pause frame will resume transmitting any pending packets. To prevent a pause frame from stopping all traffic on the entire network, Ethernet switches and routers do not propagate pause control frames in Full-Duplex mode. The pause operation only applies to the recipient.

A sample network is shown in Figure 10-1. If Computer A were to be transmitting too much data to the ENC28J60 in Full-Duplex mode, the ENC28J60 could transmit a pause control frame to stop the data which is being sent to it. The Ethernet switch would take the pause frame and stop sending data to the ENC28J60. If Computer A continues to send data, the Ethernet switch will buffer the data so it can be transmitted later when its pause timer expires. If the Ethernet switch begins to run out of buffer space, it will likely transmit a pause control frame of its own to Computer A. If, for some reason, the Ethernet switch does not generate a pause control frame of its own, or one of the nodes does not properly handle the pause frame it receives, then packets will inevitably be dropped. In any event, any communication between Computer A and Computer B will always be completely unaffected.

# FIGURE 10-1:

SAMPLE FULL-DUPLEX NETWORK



To enable flow control on the ENC28J60 in Full-Duplex mode, the host controller must set the TXPAUS and RXPAUS bits in the MACON1 register. Then, at any time that the receiver buffer is running out of space, the host controller should turn flow control on by writing the value 02h to the EFLOCON register. The hardware will periodically transmit pause frames loaded with the pause timer value specified in the EPAUS registers. The host controller can continue to transmit its own packets without interfering with the flow control hardware.

When space has been made available for more packets in the receive buffer, the host controller should turn flow control off by writing the value 03h to the EFLOCON register. The hardware will send one last pause frame loaded with a pause timer value of 0000h. When the pause frame is received by the remote node, it will resume normal network operations. When RXPAUS is set in the MACON1 register and a valid pause frame arrives with a non-zero pause timer value, the ENC28J60 will automatically inhibit transmissions. If the host controller sets the ECON1.TXRTS bit to send a packet, the hardware will simply wait until the pause timer expires before attempting to send the packet and subsequently clearing the TXRTS bit. Normally, the host controller will never know that a pause frame has been received. However, if it is desirable to the host controller to know when the MAC is paused or not, it should set the PASSALL bit in MACON1 and then manually interpret the pause control frames which may arrive.

#### REGISTER 10-1: EFLOCON: ETHERNET FLOW CONTROL REGISTER

	U-0	U-0	U-0	U-0	U-0	R-0	R/W-0	R/W-0					
	—	_	—	—	_	FULDPXS	FCEN1	FCEN0					
	bit 7							bit 0					
bit 7-3	Unimplem	ented: Rea	<b>d as</b> '0'										
bit 2	FULDPXS	: Read-Only	MAC Full-E	Duplex Shad	low bit								
		<ul> <li>MAC is configured for Full-Duplex mode (MACON3.FULDPX is set)</li> <li>MAC is configured for Half-Duplex mode (MACON3.FULDPX is clear)</li> </ul>											
bit 1-0	FCEN1:FC	<b>CEN1:FCEN0:</b> Flow Control Enable bits											
	When FUL	When FULDPXS = 1:											
	11 = Send	11 = Send one pause frame with a '0' timer value and then turn flow control off											
			pause frame	es will be aut	omatically t	ransmitted)							
	01 = Resei												
	When FUL	DPXS = 0:											
	11 = Flow												
	10 = Flow	control off											
	01 = Flow												
	00 = Flow	control off											
	· ·												
	Legend:												
	R = Reada		W = V	Vritable bit		mplemented	bit, read as '	0'					
	-n = Value	at POR	'1' = B	Bit is set	'0' = Bit	is cleared	x = Bit is u	nknown					

TABLE 10-1: SUMMARY OF REGISTERS USED WITH FLOW CONTROL

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on page
ECON1	TXRST	RXRST	DMAST	CSUMEN	TXRTS	RXEN	BSEL1	BSEL0	13
MACON1	—	—		LOOPBK	TXPAUS	RXPAUS	PASSALL	MARXEN	14
MABBIPG	—	Back-to-Ba	ck Inter-Pack	et Gap (BBI	PG<6:0>)				14
EFLOCON	—	—	_	—	_	FULDPXS	FCEN1	FCEN0	14
EPAUSL	Pause Time	ause Timer Value Low Byte (EPAUS<7:0>)							
EPAUSH	Pause Time	er Value High	n Byte (EPAL	JS<15:8>)					14

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used.

NOTES:


# 11.0 **RESET**

The ENC28J60 differentiates between various kinds of Reset:

- Power-on Reset (POR)
- System Reset
- Transmit Only Reset
- Receive Only Reset
- Miscellaneous MAC and PHY Subsystem Resets

A simplified block diagram of the On-Chip Reset Circuit is shown in Figure 11-1.





© 2004 Microchip Technology Inc.

# 11.1 Power-on Reset (POR)

A Power-on Reset pulse is generated on-chip whenever VDD rises above a certain threshold. This allows the device to start in the initialized state when VDD is adequate for operation.

The POR circuitry is always enabled. As a result, most applications do not need to attach any external circuitry to the RESET pin to ensure a proper Reset at powerup. The RESET pin's internal weak pull-up will maintain a logical high level on the pin during normal device operation.

To ensure proper POR operation, a minimum rise rate for VDD is specified (parameter D004). The application circuit must meet this requirement to allow the Oscillator Start-up Timer and CLKOUT functions to reset properly.

After a Power-on Reset, the contents of the dual port buffer memory will be unknown. However, all registers will be loaded with their specified Reset values. Certain portions of the ENC28J60 must not be accessed immediately after a POR. See **Section 2.2 "Oscillator Start-up Timer"** for more information.

# 11.2 System Reset

The System Reset of ENC28J60 can be accomplished by either the RESET pin, or through the SPI interface.

The RESET pin provides an asynchronous method for triggering an external Reset of the device. A Reset is generated by holding the RESET pin low. The ENC28J60 has a noise filter in the RESET path which detects and ignores small pulses. When the RESET pin is held high, the ENC28J60 will operate normally.

The ENC28J60 can also be reset via the SPI using a system command. See **Section 4.0 "Serial Peripheral Interface (SPI)"**.

The RESET pin will not be driven low by any internal Resets, including the System Command Reset via the SPI interface.

After a System Reset, all PHY registers should not be read or written to until at least 50  $\mu$ s have passed since the Reset has ended. All registers will revert to their Reset default values. The dual port buffer memory will maintain state throughout the System Reset.

# 11.3 Transmit Only Reset

The Transmit Only Reset is performed by writing a '1' to the TXRST bit in the ECON1 register using the SPI interface. If a packet was being transmitted when the TXRST bit was set, the hardware will automatically clear the TXRTS bit and abort the transmission. This action resets the transmit logic only. The System Reset automatically performs the Transmit Only Reset. Other register and control blocks, such as buffer management and host interface, are not affected by a Transmit Only Reset event. When the host controller wishes to return to normal operation, it should clear the TXRST bit.

# 11.4 Receive Only Reset

The Receive Only Reset is performed by writing a '1' to the RXRST bit in the ECON1 register using the SPI interface. If packet reception was enabled (the RXEN bit was set) when RXRST was set, the hardware will automatically clear the RXEN bit. If a packet was being received, it would be immediately aborted. This action resets receive logic only. The System Reset automatically performs Receive Only Reset. Other register and control blocks, such as the buffer management and host interface blocks, are not affected by a Receive Only Reset event. When the host controller wishes to return to normal operation, it should clear the RXRST bit.

### 11.5 MAC and PHY Subsystem Resets

The PHY module may be reset by writing a '1' to the PRST bit in the PHCON1 register. All the PHY register contents will revert to their Reset defaults. Unlike other Resets, the PHY cannot be removed from Reset immediately after setting PRST. The PHY requires a delay, after which the hardware automatically clears the PRST bit. The host controller should poll PRST and wait for it to become clear before using the PHY after issuing a Reset. The System Reset automatically performs this PHY Reset.

There are a total of nine Resets available to the MAC subsystem. Six Reset bits are found in the MACON2 register:

- MARST
- RNDRST
- MARXRST
- RFUNRST
- MATXRST
- TFUNRST

# There are also two Reset bits located in the MAPHSUP register (RSTINTFC and RSTRMII) and one in MICON (RSTMII). Setting any of these bits will cause some portion of the ENC28J60 to stop functioning properly. It is recommended that all bits be kept clear.

A System Reset automatically performs all of these Subsystem Resets. However, after a System Reset, the global MAC Reset bit, MARST, remains set. The host controller must clear this bit before attempting to transmit packets, receive packets or access any PHY register.

The MAC and PHY Reset bits are explained in Register 11-1, Register 11-2 and Register 11-3. The RSTMII bit is shown in Register 3-3 (page 21).

#### REGISTER 11-1: MACON2: MAC CONTROL REGISTER 2

				_			
R/W-1	R/W-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0
MARST	RNDRST	—	_	MARXRST	RFUNRST	MATXRST	TFUNRST
bit 7							bit 0

bit 7	MARST: MAC Reset t	hit	
	1 = Entire MAC is hel		
	0 = Normal operation		
bit 6	RNDRST: MAC Rand	om Number Generator Re	eset bit
	<ol> <li>1 = Random number</li> <li>0 = Normal operation</li> </ol>	-	it function is held in Reset
bit 5-4	Unimplemented: Rea	ad as '0'	
bit 3	MARXRST: MAC Cor	ntrol Sublayer/Receive Lo	gic Reset bit
	1 = MAC control subl	ayer and receiver logic ar	re held in Reset
	0 = Normal operation		
bit 2	RFUNRST: MAC Rec	eive Function Reset bit	
	1 = MAC receive logi	c is held in Reset	
	0 = Normal operation		
bit 1	MATXRST: MAC Con	trol Sublayer/Transmit Lo	gic Reset bit
	1 = MAC control subl	ayer and transmit logic a	e held in Reset
	0 = Normal operation		
bit 0	TFUNRST: MAC Tran	smit Function Reset bit	
	1 = MAC transmit log	ic is held in Reset	
	0 = Normal operation		
	Legend:		
	R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'

R = Readable bit	VV = VVritable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

# **ENC28J60**

REGISTER 11-2:	MAPHSUP:	МАС-РН	Y SUPPOR	RT REGIS	TER						
	R/W-0	U-0	U-0	R/W-1	R/W-0	U-0	U-0	R/W-0			
	RSTINTFC	_	—	r	RSTRMII	_	_	r			
	bit 7				· · · ·			bit 0			
bit 7	RSTINTFC:	nterface M	odule Reset	t bit							
	1 = RMII mo 0 = Normal c			also cleare	ed						
bit 6-5	Unimplemen	Jnimplemented: Read as '0'									
bit 4	Reserved: M	aintain as	'1'								
bit 3	RSTRMII: RM	/II Module	Reset bit								
	1 = RMII mo 0 = Normal o			is also clea	ared						
bit 2-1	Unimplemen	ted: Read	<b>as</b> '0'								
bit 0	Reserved: M	aintain as	ʻ0'								
	Legend:										
	R = Readable	e bit	W = Wr	itable bit	U = Unimp	olemented	bit, read as '	0'			
	-n = Value at	POR	'1' = Bit	is set	'0' = Bit is	cleared	x = Bit is u	nknown			

## REGISTER 11-2: MAPHSUP: MAC-PHY SUPPORT REGISTER

R/W-0	R/W-0	U-0	U-0	R-1	R/W-0	U-0	R-x			
PRST	PLOOPBK			PPWRSV	r		PDPXMD <sup>(1)</sup>			
bit 15		L		•			bit 8			
	R/W-0	U-0	U-0	U-0	U-0	U-0	U-0	U-0		
	r		_	_	_	_	_	_		
	bit 7		I					bit 0		
bit 15	<b>PRST:</b> PHY Softw 1 = PHY is proce 0 = Normal opera	ssing a So		et (automatica	lly resets to 'o	' when don	e)			
bit 14										
bit 13-12	Unimplemented:	Read as '	)'							
bit 11	PPWRSV: PHY P	ower-Dowi	n bit							
	1 = PHY is shut-o 0 = Normal opera									
bit 10	Reserved: Mainta	ain as 'o'								
bit 9	Unimplemented:	Read as 'o	)'							
bit 8	PDPXMD: PHY D	uplex Mod	e bit <sup>(1)</sup>							
	1 = PHY operate 0 = PHY operate									
	Note 1: The R	eset defau	It of PDPXN	/ID depends o	n the externa	I polarity of	the LEDB LED.			
bit 7	Reserved: Mainta	ain as '0'								

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, re	ead as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

NOTES:


# 12.0 INTERRUPTS


The ENC28J60 has multiple interrupt sources and two separate interrupt output pins to signal the occurrence of events to the host controller. The interrupt pins are designed for use by a host controller which is capable of detecting falling edges.

Interrupts are divided into two sources: control events (INT) and Wake-up on LAN (WOL) events. The EIE and EWOLIE registers contain the individual interrupt enable bits for each interrupt source, while the EIR and EWOLIR registers contain the corresponding interrupt flag bits. When an interrupt occurs, the interrupt flag is set. If the interrupt is enabled in the EIE or EWOLIE registers and the corresponding INTIE or WOLIE global interrupt enable bit is set, the appropriate INT or WOL interrupt pin will be driven low by the ENC28J60 (see Figure 12-1).

Note: Except for the LINKIF interrupt flag, interrupt flag bits are set when an interrupt condition occurs regardless of the state of its corresponding enable bit or the associated global enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt. This feature allows for software polling. When an enabled interrupt occurs, the interrupt pin will remain low until all flags which are causing the interrupt are cleared or masked off (enable bit is cleared) by the host controller. If more than one interrupt source is enabled, the host controller must poll each flag in the EIR or EWOLIR register to determine the source(s) of the interrupt. It is recommended that the Bit Field Clear (BFC) SPI command be used to reset the flag bits in the EIR and EWOLIR registers rather than the normal Write Control Register (WCR) command. This is necessary to prevent unintentionally altering a flag that changes during the write command. The BFC and WCR commands are discussed in detail in **Section 4.0** "**Serial Peripheral Interface (SPI)**".

After an interrupt occurs, the host controller should clear the global enable bit for the interrupt pin before servicing the interrupt. Clearing the enable bit will cause the interrupt pin to return to the non-asserted state (high). Doing so will prevent the host controller from missing a falling edge should another interrupt occur while the immediate interrupt is being serviced. After the interrupt has been serviced, the global enable bit may be restored. If an interrupt event occurred while the previous interrupt was being processed, the act of resetting the global enable bit will cause a new falling edge on the interrupt pin to occur.





# 12.1 INT Interrupt Enable (INTIE)

The INT Interrupt Enable bit (INTIE) is a global enable bit which allows the following interrupts to drive the INT pin:

- Receive Error Interrupt (RXERIF)
- Transmit Error Interrupt (TXERIF)
- Transmit Interrupt (TXIF)
- Link Change Interrupt (LINKIF)
- DMA Interrupt (DMAIF)
- Receive Packet Pending Interrupt (PKTIF)

When any of the above interrupts are enabled and generated, the virtual bit, INT in the ESTAT register (Register 12-1), will be set to '1'. If EIE.INTIE is '1', the INT pin will be driven low.

#### 12.1.1 INT INTERRUPT REGISTERS

The registers associated with the INT interrupts are shown in Register 12-2, Register 12-3, Register 12-4 and Register 12-5.

#### REGISTER 12-1: ESTAT: ETHERNET STATUS REGISTER

	R-0	R/C-0	R-0	R/C-0	U-0	R-0	R/C-0	R/W-0				
	INT	r	r	LATECOL	—	RXBUSY	TXABRT	CLKRDY				
	bit 7							bit 0				
bit 7	INT: INT In	terrupt Flag	g bit									
		<ul><li>1 = INT interrupt is pending</li><li>0 = No INT interrupt is pending</li></ul>										
bit 6-5	Reserved:	Maintain a	<b>s</b> '0'									
bit 4	LATECOL	Late Collis	ion Error b	it								
				bytes have b		itted						
	0 = No col	lisions after	r 64 bytes h	nave occurre	d							
bit 3	Unimplem	ented: Rea	ad as '0'									
bit 2	RXBUSY:	Receive Bu	sy bit									
		/e logic is r /e logic is lo	0	data packet								
bit 1	TXABRT:	Fransmit Ab	ort Error bi	t								
		ansmit requ		orted								
		nsmit abort										
bit 0		Clock Read										
	<ul> <li>1 = OST has expired; PHY is ready</li> <li>0 = OST is still counting; PHY is not ready</li> </ul>											
	Legend:											
	R = Reada	ble bit	C = 0	Clearable bit	U = Uni	mplemented	d bit, read as	s 'O'				
	-n = Value	at POR	'1' =	Bit is set	'0' = Bit	is cleared	r = Resei	ved bit				

# **ENC28J60**

ER 12-2:	EIE: ETH	ERNET INT	ERRUPT	ENABLE R	EGISTER			
	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
	INTIE	PKTIE	DMAIE	LINKIE	TXIE	WOLIE	TXERIE	RXERIE
	bit 7							bit 0
bit 7		bal INT Inte	•					
		interr <u>upt</u> eve le all INT pin			usly driven ł	nigh)		
bit 6	PKTIE: Re	eceive Packe	et Pending Ir	nterrupt Ena	ble bit			
		e receive pa						
		le receive pa	•	g interrupt				
bit 5		MA Interrupt						
		e DMA interi le DMA inter						
bit 4		ink Status Cl	•	upt Enable b	oit			
		e link chang	•	•				
		le link chang						
bit 3	TXIE: Trar	nsmit Enable	bit					
		e transmit in						
		le transmit ir	•					
bit 2		ilobal WOL I	•		<u>.</u>			
		WOL interru le all WOL p				high)		
bit 1		Fransmit Erro	•					
		e transmit er	•					
	0 = Disab	le transmit e	rror interrup	t				
bit 0	RXERIE: R	Receive Erro	or Interrupt E	nable bit				
		e receive err						
	0 = Disab	le receive er	ror interrupt					
	Legend:							]
	R = Reada	able bit	W = W	/ritable bit	U = Unin	nplemented	bit, read as '	0'

# REGISTER 12-2: EIE: ETHERNET INTERRUPT ENABLE REGISTER

-n = Value at POR

'1' = Bit is set

'0' = Bit is cleared

x = Bit is unknown

# **ENC28J60**

					· /				
	U-0	R-0	R/C-0	R-0	R/C-0	R-0	R/C-0	R/C-0	
		PKTIF	DMAIF	LINKIF	TXIF	WOLIF	TXERIF	RXERIF	
	bit 7							bit 0	
bit 7	Unimplem	ented: Rea	<b>d as</b> '0'						
bit 6	PKTIF: Receive Packet Pending Interrupt Flag bit								
	1 = Receive buffer contains one or more unprocessed packets; cleared when PKTDEC is set								
	0 = Receive buffer is empty								
bit 5	DMAIF: DMA Interrupt Flag bit								
	1 = DMA copy or checksum calculation has completed								
	0 = No DMA interrupt is pending								
bit 4	LINKIF: Link Change Interrupt Flag bit								
	1 = PHY reports that the link status has changed; read PHIR register to clear								
	0 = Link status has not changed								
bit 3	<b>TXIF:</b> Transmit Interrupt Flag bit 1 = Transmit request has ended								
		•		a					
bit 2	<ul> <li>0 = No transmit interrupt is pending</li> <li>WOLIF: WOL Interrupt Flag bit</li> </ul>								
	1 = Wake-up on LAN interrupt is pending								
	0 = No Wake-up on LAN interrupt is pending								
bit 1		•	or Interrupt F						
	1 = A transmit error has occurred								
	0 = No trai	nsmit error h	nas occurred	ł					
bit 0	RXERIF: R	eceive Erro	r Interrupt F	lag bit					
					ufficient buff	fer space or	the packet o	ount is 255	
	0 = No rec	eive error ir	nterrupt is pe	ending					
	Legend:								

C = Clearable bit

'1' = Bit is set

R = Readable bit

-n = Value at POR

U = Unimplemented bit, read as '0'

x = Bit is unknown

'0' = Bit is cleared

R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	
r	r	r	r	r	r	r	r	
bit 15							bit 8	
	R/W->	R/W-x	R/W-0	R/W-0	R/W-x	R/W-x	R/W-0	R/W-0
	r	r	r	PLNKIE	r	r	PGEIE	r
	bit 7							bit
oit 15-6	Reserved: W	rite as 'o', igno	re on read					
oit 5	Reserved: Maintain as '0'							
oit 4	PLNKIE: PHY Link Change Interrupt Enable bit							
	1 = PHY link 0 = PHY link	change interru change interru						
bit 3-2	Reserved: Write as '0', ignore on read							
bit 1	PGEIE: PHY Global Interrupt Enable bit							
	<ul> <li>1 = PHY interrupts are enabled</li> <li>0 = PHY interrupts are disabled</li> </ul>							
bit 0	Reserved: Maintain as '0'							
Legend	:							
R = Readable bit W = Writable bit		ebit r=	Reserved bit		U = Unimplemented bit, read as '0'			
-n = Value at POR '1' = Bit is set		et 'O'	'0' = Bit is cleared			x = Bit is unknown		

#### R-x R-x R-x R-x R-x R-x R-x R-x r r r r r r r r bit 15 bit 8 R-0 R/SC-0 R/SC-0 R-0 R-x R-x R-0 R-x PLNKIF PGIF r r r r r r bit 7 bit 0

#### bit 15-5 Reserved

- bit 4 PLNKIF: PHY Link Change Interrupt Flag bit
  - 1 = PHY link status has changed since PHIR was last read; resets to '0' when read
  - 0 = PHY link status has not changed since PHIR was last read

#### bit 3 Reserved

- bit 2 PGIF: PHY Global Interrupt Flag bit
  - 1 = One or more enabled PHY interrupts have occurred since PHIR was last read; resets to '0' when read 0 = No PHY interrupts have occurred
- bit 1-0 Reserved

Legend:			
R = Readable bit	SC = Self-clearing bit	U = Unimplemented bit, read	as '0'
r = Reserved bit	'1' = Bit is set on POR	'0' = Bit is cleared on POR	x = Bit is unknown

#### 12.1.2 RECEIVE ERROR INTERRUPT FLAG (RXERIF)

The Receive Error Interrupt Flag (RXERIF) is used to indicate a receive buffer overflow condition. Alternately, this interrupt may indicate that too many packets are in the receive buffer and more cannot be stored without overflowing the EPKTCNT register.

When a packet is being received and the receive buffer runs completely out of space, or EPKTCNT is 255 and cannot be incremented, the packet being received will be aborted (permanently lost) and the EIR.RXERIF bit will be set to '1'. Once set, RXERIF can only be cleared by the host controller or by a Reset condition. If the receive error interrupt and INT interrupt are enabled (EIE.RXERIE = 1 and EIE.INTIE = 1), an interrupt is generated by driving the INT pin low. If the receive error interrupt is not enabled (EIE.RXERIE = 0 or EIE.INTIE = 0), the host controller may poll the ENC28J60 for the RXERIF and take appropriate action.

Normally, upon the receive error condition, the host controller would process any packets pending from the receive buffer and then make additional room for future packets by advancing the ERXRDPT registers (low byte first) and decrementing the EPKTCNT register. See **Section 7.2.4 "Freeing Receive Buffer Space"** for more information on processing packets. Once processed, the host controller should use the BFC command to clear the EIR.RXERIF bit.

#### 12.1.3 TRANSMIT ERROR INTERRUPT FLAG (TXERIF)

The Transmit Error Interrupt Flag (TXERIF) is used to indicate that a transmit abort has occurred. An abort can occur because of any of the following:

- 1. Excessive collisions occurred as defined by the Retransmission Maximum (RETMAX) bits in the MACLCON1 register.
- 2. A late collision occurred as defined by the Collision Window (COLWIN) bits in the MACLCON2 register.
- 3. A collision after transmitting 64 bytes occurred (ESTAT.LATECOL set).
- The transmission was unable to gain an opportunity to transmit the packet because the medium was constantly occupied for too long. The deferral limit (2.4287 ms) was reached and the MACON4.DEFER bit was clear.
- An attempt to transmit a packet larger than the maximum frame length defined by the MAMXFL registers was made without setting the MACON3.HFRMEN bit or per packet POVERRIDE and PHUGEEN bits.

Upon any of these conditions, the EIR.TXERIF flag is set to '1'. Once set, it can only be cleared by the host controller or by a Reset condition. If the transmit error interrupt is enabled (EIE.TXERIE = 1 and EIE.INTIE = 1), an interrupt is generated by driving the INT pin low for one OSC1 period. If the transmit error interrupt is not enabled (EIE.TXERIE = 0 or EIE.INTIE = 0), the host controller may poll the ENC28J60 for the TXERIF and take appropriate action. Once the interrupt is processed, the host controller should use the BFC command to clear the EIR.TXERIF bit.

After a transmit abort, the TXRTS bit will be cleared, the ESTAT.TXABRT bit will be set and the transmit status vector will be written at ETXND + 1. The MAC will not automatically attempt to retransmit the packet. The host controller may wish to read the transmit status vector and LATECOL bit to determine the cause of the abort. After determining the problem and solution, the host controller should clear the LATECOL (if set) and TXABRT bits so that future aborts can be detected accurately.

In Full-Duplex mode, condition 5 is the only one that should cause this interrupt. Collisions and other problems related to sharing the network are not possible on full-duplex networks. The conditions which cause the transmit error interrupt meet the requirements of the transmit interrupt. As a result, when this interrupt occurs, TXIF will also be simultaneously set.

#### 12.1.4 TRANSMIT INTERRUPT FLAG (TXIF)

The Transmit Interrupt Flag (TXIF) is used to indicate that the requested packet transmission has ended (ECON1.TXRTS has transitioned from '1' to '0'). Upon transmission completion, abort or transmission cancellation by the host controller, the EIR.TXIF flag will be set to '1'. If the host controller did not clear the TXRTS bit and the ESTAT.TXABRT bit is not set, then the packet was successfully transmitted. Once TXIF is set, it can only be cleared by the host controller or by a Reset condition. If the transmit interrupt is enabled (EIE.TXIE = 1 and EIE.INTIE = 1), an interrupt is generated by driving the INT pin low. If the transmit interrupt is not enabled (EIE.TXIE = 0 or EIE.INTIE = 0), the host controller may poll the ENC28J60 for the TXIF bit and take appropriate action. Once processed, the host controller should use the BFC command to clear the EIR.TXIF bit.

#### 12.1.5 LINK CHANGE INTERRUPT FLAG (LINKIF)

The LINKIF indicates that the link status has changed. The actual current link status can be obtained from the PHSTAT1.LLSTAT or PHSTAT2.LSTAT (see Register 3-6 and Register 3-7). Unlike other interrupt sources, the link status change interrupt is created in the integrated PHY module; additional steps must be taken to enable it.

By Reset default, LINKIF is never set for any reason. To receive it, the host controller must set the PHIE.PLNKIE and PGEIE bits. After setting the two PHY interrupt enable bits, the LINKIF bit will then shadow the contents of the PHIR.PGIF bit. The PHY only supports one interrupt, so the PGIF bit will always be the same as the PHIR.PLNKIF bit (when both PHY enable bits are set).

Once LINKIF is set, it can only be cleared by the host controller or by a Reset. If the link change interrupt is enabled (EIE.LINKIE = 1, EIE.INTIE = 1, PHIE.PLNKIE = 1 and PHIE.PGEIE = 1), an interrupt will be generated by driving the INT pin low. If the link change interrupt is not enabled (EIE.LINKIE = 0, EIE.INTIE = 0, PHIE.PLNKIE = 0 or PHIE.PGEIE = 0), the host controller may poll the ENC28J60 for the PHIR.PLNKIF bit and take appropriate action.

The LINKIF bit is read-only. Because reading from PHY registers requires non-negligible time, the host controller may instead set PHIE.PLNKIE and PHIE.PGEIE and then poll the EIR.LINKIF bit. Performing an MII read on the PHIR register will clear the LINKIF, PGIF and PLNKIF bits automatically and allow for future link status change interrupts. See **Section 3.3 "PHY Registers"** for information on accessing the PHY registers.

#### 12.1.6 DMA INTERRUPT FLAG (DMAIF)

The DMA interrupt indicates that the DMA module has completed its memory copy or checksum calculation (ECON1.DMAST has transitioned from '1' to '0'). Additionally, this interrupt will be caused if the host controller cancels a DMA operation by manually clearing the DMAST bit. Once set, DMAIF can only be cleared by the host controller or by a Reset condition. If the DMA interrupt is generated by driving the INT pin low. If the DMA interrupt is not enabled (EIE.DMAIE = 1 and EIE.INTIE = 1), an interrupt is not enabled (EIE.DMAIE = 0 or EIE.INTIE = 0), the host controller may poll the ENC28J60 for the DMAIF and take appropriate action. Once processed, the host controller should use the BFC command to clear the EIR.DMAIF bit.

#### 12.1.7 RECEIVE PACKET PENDING INTERRUPT FLAG (PKTIF)

The Receive Packet Pending Interrupt Flag (PKTIF) is used to indicate the presence of one or more data packets in the receive buffer and to provide a notification means for the arrival of new packets. When the receive buffer has at least one packet in it, EIR.PKTIF will be set. In other words, this interrupt flag will be set anytime the Ethernet Packet Count register (EPKTCNT) is non-zero. If the receive packet pending interrupt is enabled (EIE.PKTIE = 1 and EIE.INTIE = 1), an interrupt will be generated by driving the INT pin low whenever a new packet is successfully received and written into the receive buffer. If the receive packet pending interrupt is not enabled (EIE.PKTIE = 0 or EIE.INTIE = 0), the host controller will not be notified when new packets arrive. However, it may poll the PKTIF bit and take appropriate action.

The PKTIF bit can only be cleared by the host controller or by a Reset condition. In order to clear PKTIF, the EPKTCNT register must be decremented to '0'. See **Section 7.2 "Receiving Packets"** for more information about clearing the EPKTCNT register. If the last data packet in the receive buffer is processed, EPKTCNT will become zero and the PKTIF bit will automatically be cleared.

# 12.2 Wake-up on LAN Interrupt (WOLIE/WOLIF)

The WOL interrupt is designed to cause a wake-up event for the host controller. The WOL interrupt is a multisource interrupt and controls the WOL interrupt pin. WOL interrupts are not affected by the EIE.INTIE configuration.

There are a total of seven different conditions that can cause this interrupt. The EWOLIE bits allow the individual conditions to be enabled. If multiple bits are set, any of the enabled conditions will be able to generate the WOL interrupt. However, the WOL filter logic is applied after the receive filter logic. As a result, any packet which is rejected as a result of the receive filter configuration (see **Section 8.0 "Receive Filters"**) will not be able to cause a WOL interrupt. When any of the seven WOL conditions are detected, the associated interrupt flag in the EWOLIR register will be set. If the associated interrupt enable is set in EWOLIE, then the EIR.WOLIF bit will also become set. If the global WOL interrupt enable bit is set (EIR.WOLIF), then an interrupt will be generated by driving the WOL pin low. If the WOL interrupt is not enabled (EIE.WOLIE = 0 or the associated bit in EWOLIE = 0), the host controller may poll the EWOLIR register and take appropriate action when the desired flag becomes set. Normally, upon receiving the WOLIF interrupt, the host controller would come out of Sleep and check the EWOLIR register for the actual source(s) of the interrupt. Depending on the application requirements, the host controller may either disable further WOLIF interrupts or keep it enabled and go back to Sleep. Once the interrupt is processed, the host controller should use the BFC command to clear the EIR.WOLIF bit and associated EWOLIR bits.

Note: When using the WOL interrupt, care should be taken to prevent the receive buffer from filling up without waking the host controller. If the receive buffer becomes full, without meeting any of the WOL criteria, all additional incoming packets will be aborted. Aborted packets are not able to cause the WOL interrupt, even if they meet the configured criteria. As a result, the WOL interrupt would never be generated.

#### 12.2.1 WOL INTERRUPT REGISTERS

The registers associated with the WOL interrupts are shown in Register 12-6 and Register 12-7. The interrupt flag bits are set when an interrupt condition occurs regardless of the state of its corresponding enable bit. This feature allows for software polling.

REGISTER 12-6:	EWOLIE: ETHERNET WAKE-UP ON LAN INTERRUPT ENABLE REGISTER

	R/W-0	R/W-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
	UCWOLIE	AWOLIE	—	PMWOLIE	MPWOLIE	HTWOLIE	MCWOLIE	BCWOLIE
	bit 7			•			•	bit 0
bit 7				AN Interrupt				
				AN interrupt				
bit 6			•	LAN Interru		+		
DILO		•		on LAN inter	•	L		
				on LAN inter	•			
bit 5	Unimpleme	ented: Read	<b>d as</b> '0'					
bit 4				ıp on LAN In		ole bit		
				up on LAN in				
h:+ 0				up on LAN ir		la h:4		
bit 3		•		p on LAN Int p on LAN int	•			
		0		ip on LAN in				
bit 2	HTWOLIE:	Hash Table	Wake-up o	on LAN Interi	upt Enable	bit		
				on LAN inter	•			
			•	on LAN inter	•			
bit 1				e-up on LAN e-up on LAN		hable bit		
				e-up on LAN				
bit 0	BCWOLIE:	Broadcast	Packet Wal	ke-up on LAI	V Interrupt E	nable bit		
				ke-up on LAI				
	0 = Disable	e Broadcast	Packet Wa	ike-up on LA	N interrupt			
	Legend:	. 1 . 1. 14					hit was d	01
	R = Readat			Vritable bit		•	bit, read as	
	-n = Value a	at POR	'1' = E	Bit is set	0' = Bit i	s cleared	x = Bit is u	nknown

REGISTER 12-7:	EWOLIR: I (FLAG) RE		T WAKE-I	JP ON LAN	INTERRU	IPT REQU	EST		
	R/C-0	R/C-0	U-0	R/C-0	R/C-0	R/C-0	R/C-0	R/C-0	
	UCWOLIF	AWOLIF	—	PMWOLIF	MPWOLIF	HTWOLIF	MCWOLIF	BCWOLIF	
	bit 7							bit 0	
bit 7	1 = A pack	et was rece	ived with a	AN Interrupt destination a the local MA	address mate			dress	
bit 6	1 = A pack	ny Packet \ et was rece kets have b	ived	i LAN Interru ed	pt Flag bit				
bit 5	Unimpleme	ented: Read	<b>d as</b> '0'						
bit 4	1 = A pack	et was rece	ived which	ip on LAN In passed the p ern match cri	attern matcl	h filter critie			
bit 3	1 = A Magi	c Packet fo	r the local N	p on LAN Int /IAC address al MAC addre	was receive	ed			
bit 2	1 = A pack	et was rece	ived which	on LAN Interr passed the h	hash table fil		ved		
bit 1	1 = A pack	<ul> <li>0 = No packets matching the hash table filter criteria have been received</li> <li>MCWOLIF: Multicast Packet Wake-up on LAN Interrupt Flag bit</li> <li>1 = A packet was received with a multicast destination address</li> <li>0 = No packets with a multicast destination address have been received</li> </ul>							
bit 0	1 = A pack 0 = No pac	et was rece	ived with a	ke-up on LAN destination a destination a	address of F	F-FF-FF-FF			
	Legend:	ala hit	0 0	laarahla hit		nlomontod	hit road oo	·0'	

- <b>J</b>			
R = Readable bit	C = Clearable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

NOTES:

#### 13.0 DIRECT MEMORY ACCESS CONTROLLER

The ENC28J60 incorporates a dual purpose DMA controller which can be used to copy data between locations within the 8-Kbyte memory buffer. It can also be used to calculate a 16-bit checksum which is compatible with various industry standard protocols, including TCP and IP.

When a DMA operation begins, the EDMAST register pair is copied into an internal source pointer. The DMA will execute on one byte at a time and then increment the internal source pointer. However, if a byte is processed and the internal source pointer is equal to the receive buffer end pointer, ERXND, the source pointer will not be incremented. Instead, the internal source pointer will be loaded with the receive buffer start pointer, ERXST. In this way, the DMA will follow the circular FIFO structure of the receive buffer and received packets can be processed using one operation. The DMA operation will end when the internal source pointer matches the EDMAND pointer.

While any DMA operation is in progress, the DMA pointers and the ECON1.CSUMEN bit should not be modified. The DMA operation can be canceled at any time by clearing the ECON1.DMAST bit. No registers will change; however, some memory bytes may already have been copied if a DMA copy was in progress.

- Note 1: If the EDMAND pointer cannot be reached because of the receive buffer wrapping behavior, the DMA operation will never end.
  - 2: By design, the DMA module cannot be used to copy only one byte (EDMAST = EDMAND). An attempt to do so will overwrite all memory in the buffer and may never end.

#### 13.1 Copying Memory

To copy memory within the buffer:

- Appropriately program the EDMAST, EDMAND and EDMADST register pairs. The EDMAST registers should point to the first byte to copy from, the EDMAND registers should point to the last byte to copy and the EDMADST registers should point to the first byte in the destination range. The destination range will always be linear, never wrapping at any values except from 8191 to 0 (the 8-Kbyte memory boundary). Extreme care should be taken when programming the start and end pointers to prevent a never ending DMA operation which would overwrite the entire 8-Kbyte buffer.
- If an interrupt at the end of the copy process is desired, set EIE.DMAIE and EIE.INTIE and clear EIR.DMAIF.
- 3. Verify that ECON1.CSUMEN is clear.
- 4. Start the DMA copy by setting ECON1.DMAST.

If a transmit operation is in progress (TXRTS set) while the DMAST bit is set, the ENC28J60 will wait until the transmit operation is complete before attempting to do the DMA copy. This possible delay is required because the DMA and transmission engine share the same memory access port.

When the copy is complete, the DMA hardware will clear the DMAST bit, set the DMAIF bit and generate an interrupt (if enabled). The pointers and the EDMACS registers will not be modified.

After the DMA module has been initialized and has begun its copy, two main clock cycles will be required for each byte copied. As a result, if a maximum size 1518-byte packet was copied, the DMA module would require slightly more than  $121.44 \,\mu$ s to complete. The time required to copy a minimum size packet of 64 bytes would be dominated by the time required to configure the DMA.

#### 13.2 Checksum Calculations

The checksum calculation logic treats the source data as a series of 16-bit big-endian integers. If the source range contains an odd number of bytes, a padding byte of 00h is effectively added to the end of the series for purposes of calculating the checksum. The calculated checksum is the 16-bit one's complement of the one's complement sum of all 16-bit integers. For example, if the bytes included in the checksum were {89h, ABh, CDh}, the checksum would begin by computing 89ABh + CD00h. A carry out of the 16th bit would occur in the example, so in 16-bit one's complement arithmetic, it would be added back to the first bit. The resulting value of 56ACh would finally be complemented to achieve a checksum of A953h.

To calculate a checksum:

- Program the EDMAST and EDMAND register pairs to point to the first and last bytes of buffer data to be included in the checksum. Care should be taken when programming these pointers to prevent a never ending checksum calculation due to receive buffer wrapping.
- 2. To generate an optional interrupt when the checksum calculation is done, clear EIR.DMAIF, set EIE.DMAIE and set EIE.INTIE.
- 3. Start the calculation by setting ECON1.CSUMEN and ECON1.DMAST.

When the checksum is finished being calculated, the hardware will clear the DMAST bit, set the DMAIF bit and an interrupt will be generated if enabled. The DMA

pointers will not be modified and no memory will be written to. The EDMACSH and EDMACSL registers will contain the calculated checksum. The host controller may write this value into a packet, compare this value with a received checksum, or use it for other purposes.

Various protocols, such as TCP and IP, have a checksum field inside a range of data which the checksum covers. If such a packet is received and the host controller needs to validate the checksum, it can do the following:

- 1. Read the checksum from the packet and save it to a temporary location
- 2. Write zeros to the checksum field.
- 3. Calculate a new checksum using the DMA controller.
- 4. Compare the results with the saved checksum from step 1.

Writing to the receive buffer is permitted when the write address is protected by means of the ERXRDPT pointers. See **Section 7.2** "**Receiving Packets**" for additional information.

The IP checksum has unique mathematical properties which may be used in some cases to reduce the processing requirements further. Writing to the receive buffer may be unnecessary in some applications.

When operating the DMA in Checksum mode, it will take one main clock cycle for every byte included in the checksum. As a result, if a checksum over 1446 bytes were performed, the DMA module would require slightly more than 57.84  $\mu$ s to complete the operation.

Register Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on page
EIE	INTIE	PKTIE	DMAIE	LINKIE	TXIE	WOLIE	TXERIE	RXERIE	13
EIR	—	PKTIF	DMAIF	LINKIF	TXIF	WOLIF	TXERIF	RXERIF	13
ECON1	TXRST	RXRST	DMAST	CSUMEN	TXRTS	RXEN	BSEL1	BSEL0	13
ERXNDL	RX End Lov	w Byte (ERX	(ND<7:0>)						13
ERXNDH	—	_	_	RX End Hig	h Byte (ER	XND<12:8	>)		13
EDMASTL	DMA Start I	_ow Byte (El	DMAST<7:0	)					13
EDMASTH	_			DMA Start I	High Byte (I	EDMAST<	12:8>)		13
EDMANDL	DMA End L	ow Byte (ED	MAND<7:0	>)					13
EDMANDH	—	_	_	DMA End H	ligh Byte (E	DMAND<1	12:8>)		13
EDMADSTL	DMA Destir	nation Low E	Byte (EDMAI	DST<7:0>)					13
EDMADSTH	_	— — DMA Destination High Byte (EDMADST<12:8>)						13	
EDMACSL	DMA Check	ksum Low B	yte (EDMAC	CS<7:0>)					13
EDMACSH	DMA Check	ksum High B	yte (EDMA	CS<15:8>)					13
Lonondi		unimplemented and or (c). Checked cells are not used with the DMA controller							

#### TABLE 13-1: SUMMARY OF REGISTERS ASSOCIATED WITH THE DMA CONTROLLER

Legend: — = unimplemented, read as '0'. Shaded cells are not used with the DMA controller.

#### 14.0 POWER-DOWN

The ENC28J60 may be commanded to power-down via the SPI interface. When powered down, it will no longer be able to transmit and receive any packets.

To maximize power savings:

- 1. Turn off packet reception by clearing ECON1.RXEN.
- 2. Wait for any in-progress packets to finish being received by polling ESTAT.RXBUSY. This bit should be clear before proceeding.
- 3. Wait for any current transmissions to end by confirming ECON1.TXRTS is clear.
- 4. Set ECON2.VRPS (if not already set).
- 5. Enter Sleep by setting ECON2.PWRSV. All MAC, MII and PHY registers become inaccessible as a result. Setting PWRSV also clears ESTAT.CLKRDY automatically.

In Sleep mode, all registers and buffer memory will maintain their states. The ETH registers and buffer memory will still be accessible by the host controller. Additionally, the clock driver will continue to operate. The CLKOUT function will be unaffected (see **Section 2.3 "CLKOUT Pin"**).

When normal operation is desired, the host controller must perform a slightly modified procedure:

- 1. Wake-up by clearing ECON2.PWRSV.
- Wait at least 300 μs for the PHY to stabilize. To accomplish the delay, the host controller may poll ESTAT.CLKRDY and wait for it to become set.
- 3. Restore receive capability by setting ECON1.RXEN.

After leaving Sleep mode, there is a delay of many milliseconds before a new link is established (assuming an appropriate link partner is present). The host controller may wish to wait until the link is established before attempting to transmit any packets. The link status can be determined by polling the PHSTAT2.LSTAT bit. Alternatively, the link change interrupt may be used if it is enabled. See Section 12.1.5 "Link Change Interrupt Flag (LINKIF)" for additional details.

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on page
ESTAT	INT	r	r	LATECOL	_	RXBUSY	TXABRT	CLKRDY	13
ECON2	AUTOINC	PKTDEC	PWRSV	—	VRPS	—	_	—	13
ECON1	TXRST	RXRST	DMAST	CSUMEN	TXRTS	RXEN	BSEL1	BSEL0	13

#### TABLE 14-1: SUMMARY OF REGISTERS USED WITH POWER-DOWN

**Legend:** — = unimplemented, read as '0', r = reserved bit. Shaded cells are not used for power-down.

NOTES:

#### 15.0 BUILT-IN SELF-TEST CONTROLLER

bit

bit

bit

bit

bit

The ENC28J60 features a Built-in Self-Test (BIST) module which is designed to confirm proper operation of each bit in the 8-Kbyte memory buffer. Although it is primarily useful for testing during manufacturing, it remains present and available for diagnostic purposes by the user. The controller writes to all locations in the buffer memory and requires several pieces of hardware shared by normal Ethernet operations. Thus, the BIST should only be used on Reset or after necessary hardware is freed. When the BIST is used, the ECON1 register's DMAST, RXEN and TXRTS bits should all be clear.

The BIST controller is operated through four registers:

- EBSTCON register (control and status register)
- EBSTSD register (fill seed/initial shift value)
- EBSTCSH and EBSTCSL registers (high and low bytes of generated checksum)

The EBSTCON register (Register 15-1) controls the module's overall operation, selecting the testing modes and starting the self-test process. The bit pattern for memory tests is provided by the EBSTSD seed register; its content is either used directly, or as the seed for a pseudo-random number generator, depending on the Test mode.

#### REGISTER 15-1: EBSTCON: SELF-TEST CONTROL REGISTER

				<b>D</b> 444 o		<b>D</b> 444 A	
R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
PSV2	PSV1	PSV0	PSEL	TMSEL1	TMSEL0	TME	BISTST
bit 7							bit (
-	SV0: Pattern S	Shift Value b	its				
	<u>/ISEL = 10:</u>						
	in EBSTSD wi		y this amour	nt after writin	g to each m	emory locat	ion.
-	<u>/ISEL = 00, 01</u>	<u>l or 11:</u>					
This valu	e is ignored.						
PSEL: P	ort Select bit						
1 = DM	and BIST mo	odules will s	wap ports w	hen accessii	ng the mem	ory	
0 = Nor	nal configurati	on					
TMSEL1	:TMSEL0: Tes	st Mode Sel	ect bits				
11 <b>= Ra</b>	e mode with r	andom data	fill				
10 <b>= Pa</b>	tern shift fill						
01 = Ad							
00 <b>= Ra</b>	ndom data fill						
TME: Te	st Mode Enab	le bit					
1 = Ena	ble Test mode						
0 = Disa	ble Test mode	;					
BISTST:	Built-in Self-Te	est Start/Bu	sy bit				
	in progress. c	leared auto	matically wh	en test is do	ne		
1 = Test	in progress, c						

R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

#### 15.1 Using the BIST

When the BIST controller is started, it will fill the entire buffer with the data generated for the current test configuration and it will also calculate a checksum of the data as it is written. When the BIST is complete, the EBSTCS registers will be updated with the checksum. The host controller will be able to determine if the test passed or failed by using the DMA module to calculate a checksum of all memory. The resulting checksum generated by the DMA should match the BIST checksum. If after any properly executed test the checksums differ, a hardware Fault may be suspected.

The BIST controller supports four different operations:

- Random Data Fill
- Random Data Fill with Race
- Address Fill
- Pattern Shift Fill

The ports through which the BIST and DMA modules access the dual port SRAM can be swapped for each of the four Test modes to ensure proper read/write capability from both ports.

To use the BIST:

- 1. Program the EDMAST register pair to 0000h.
- 2. Program EDMAND and ERXND register pairs to 1FFFh.
- 3. Configure the DMA for checksum generation by setting CSUMEN in ECON1.
- Write the seed/initial shift value byte to the EBSTSD register (this is not necessary if Address Fill mode is used).
- 5. Enable Test mode, select the desired test, select the desired port configuration for the test.
- 6. Start the BIST by setting EBSTCON.BISTST.
- If Random Data Fill with Race mode is not used, start the DMA checksum by setting DMAST in ECON1. The DMA controller will read the memory at the same rate the BIST controller will write to it, so the DMA can be started any time after the BIST is started.
- Wait for the DMA to complete by polling the DMAST bit or receiving the DMA interrupt (if enabled).
- 9. Compare the EDMACS registers with the EBSTCS registers.

To ensure full testing, the test should be redone with the Port Select bit, PSEL, altered. When not using Address Fill mode, additional tests may be done with different seed values to gain greater confidence that the memory is working as expected. At any time during a test, the test can be canceled by clearing the BISTST, DMAST and TME bits. While the BIST is filling memory, the EBSTSD register should not be accessed, nor should any configuration changes occur. When the BIST completes its memory fill and checksum generation, the BISTST bit will automatically be cleared.

The BIST module requires one main clock cycle for each byte that it writes into the RAM. The DMA module's checksum implementation requires the same time but it can be started immediately after the BIST is started. As a result, the minimum time required to do one test pass is slightly greater than  $327.68 \, \mu s$ .

#### 15.2 Random Data Fill Mode

In Random Data Fill mode, the BIST controller will write pseudo-random data into the buffer. The random data is generated by a Linear Feedback Shift Register (LFSR) implementation. The random number generator is seeded by the initial contents of the EBSTSD register and the register will have new contents when the BIST is finished.

Because of the LFSR implementation, an initial seed of zero will generate a continuous pattern of zeros. As a result, a non-zero seed value will likely perform a more extensive memory test. Selecting the same seed for two separate trials will allow a repeat of the same test.

#### 15.3 Random Data Fill with Race Mode

Random Data Fill with Race mode is identical to Random Data Fill mode, except that the hardware automatically sets the DMAST bit immediately after the host controller sets the BISTST bit. As a result, back-to-back memory access is tested.

#### 15.4 Address Fill Mode

In Address Fill mode, the BIST controller will write the low byte of each memory address into the associated buffer location. As an example, after the BIST is operated, the location 0000h should have 00h in it, location 0001h should have 01h in it, location 0E2Ah should have 2Ah in it and so on. With this fixed memory pattern, the BIST and DMA modules should always generate a checksum of F807h. The host controller may use Address Fill mode to confirm that the BIST and DMA modules themselves are both operating as intended.

#### 15.5 Pattern Shift Fill Mode

In Pattern Shift Fill mode, the BIST controller writes the value of EBSTSD into memory location 0000h. Before writing to location 0001h, it shifts the contents of EBSTSD to the left by the value specified by the PSV2:PSV0 bits in EBSTCON. Bits that leave the most

significant end of EBSTSD are wrapped around to the least significant side. This shift is repeated for each new address. As a result of shifting the data, a checkerboard pattern can be written into the buffer memory to confirm that adjacent memory elements do not affect each other when accessed.

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Reset Values on page
ECON1	TXRST	RXRST	DMAST	CSUMEN	TXRTS	RXEN	BSEL1	BSEL0	13
ERXNDL	RX End Lo	ow Byte (Ef	RXND<7:0>)						13
ERXNDH		_		RX End Hi	gh Byte (EF	RXND<12:8	>)		13
EDMASTL	DMA Start	Low Byte	EDMAST<7	:0>)					13
EDMASTH	—	_	_	DMA Start	High Byte (	EDMAST<1	12:8>)		13
EDMANDL	DMA End	Low Byte (	EDMAND<7	:0>)					13
EDMANDH	—	—	—	DMA End	High Byte (I	EDMAND<1	2:8>)		13
EDMACSL	DMA Chee	cksum Low	Byte (EDMA	ACS<7:0>)					13
EDMACSH	DMA Chee	cksum High	Byte (EDM	ACS<15:8>)	)				13
EBSTSD	Built-in Se	If-Test Fill S	Seed (EBST	SD<7:0>)					14
EBSTCON	PSV2	PSV1	PSV0	PSEL	TMSEL1	TMSEL0	TME	BISTST	14
EBSTCSL	Built-in Se	If-Test Che	cksum Low I	Byte (EBST	CS<7:0>)				14
EBSTCSH	Built-in Self-Test Checksum High Byte (EBSTCS<15:8>)							14	
Leaend:	_ unimplor	montod roc	d as '0' Sha	adad aalla a	ro not upod				

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used.

NOTES:

### **16.0 ELECTRICAL CHARACTERISTICS**

#### **Absolute Maximum Ratings**

VDD, VDDOSC, VDDPLL, VDDRX, VDDTX	4.0V
Storage temperature	65°C to +150°C
Ambient temperature with power applied (TA)	40°C to +85°C∢(Industrial)
	0°C to +70°C (Commercial)
Soldering temperature of leads (10 seconds)	+ <del>30</del> 0°C
RESET, CS, SCK and SI, with respect to Vss	-0.6V to 7.0V
CLKOUT, SO, TPIN+/-, TPOUT+/-, OSC1, OSC2, LEDA and LEDB, with respect to	
VCAP with respect to Vss	-0.6V to 3.0V
ESD protection on all pins	
Current sourced or sunk by LEDA, LEDB	
Current sourced or sunk by CLKOUT	
Current sourced or sunk by INT, WOL and SO	
	$\searrow$

**† Notice:** Stresses above those listed under "Maximum Ratings" may cause permanent damage to the device. This is a stress rating only and functional operation of the device at those or any other conditions above those indicated in the operational listings of this specification is not implied. Exposure to maximum rating conditions for extended periods may affect device reliability.

#### DC Characteristics: ENC28J60 (Industrial and Commercial) 16.1

DC CHA	RACTE	RISTICS	$\begin{array}{l} \textbf{Standard Operating Conditions} \\ -40^{\circ}\text{C} \leq \text{TA} \leq +85^{\circ}\text{C}, \ 3.14\text{V} \leq \text{VDD} \leq 3.45\text{V} \ (\text{Industrial}) \\ 0^{\circ}\text{C} \leq \text{TA} \leq +70^{\circ}\text{C}, \ 3.14\text{V} \leq \text{VDD} \leq 3.45\text{V} \ (\text{Commercial}) \end{array}$					
Param. No.	Sym	Characteristic	Min	Мах	Units	Conditions		
D001	Vdd	Supply Voltage	3.14	3.45	V			
D002	Vdr	Register Retention Voltage	TBD		V	Includes dual port memory)		
D003	VPOR	VDD Start Voltage to ensure internal Power-on Reset signal	_	0.7	V	See section on Rower on Reset for details		
D004	Svdd	VDD Rise Rate to ensure internal Power-on Reset signal	0.05	_	V/µs	See section on Power-on Reset for details		
	Vih	High-Level Input Voltage						
D040		SCK, <del>CS</del> , SI	2.0	5.5	V <			
D042A		OSC1	0.85 Vdd	Vdd	$\langle \mathcal{M} \rangle$			
D042		RESET	0.85 Vdd	5.5		$\overline{\mathcal{T}}$		
	VIL	Low-Level Input Voltage		$\square$	$\sum$			
D030		SCK, <del>CS</del> , SI	-0.3	~ d.8	))v			
D032A		OSC1	Vss /	0.3 VDD	V			
D032		RESET	Vss	0.8	V			
	Vol	Low-Level Output Voltage		$\langle \rangle$				
		SO, CLKOUT	$\overline{\gamma}$	->твd	V			
		INT, WOL	$/ \not{\sim}$	TBD	V			
	Voн	High-Level Output Voltage	$\sim$					
		SO, CLKOUT	∕> TBD	—	V			
		INT, WOL	TBD	—	V			
	Rpu	Weak Pull-up Resistance	74K	173K	Ω			
	ILI	Input Leakage Current						
		All I/O pins except OSC1	—	TBD	μA	$\overline{CS} = \overline{RESET} = VDD,$ VIN = VSS to VDD		
		OSC 1 pin	_	TBD	μA			
		Internal Capacitance (all inputs and outputs)	—	TBD	pF	TA = 25°C, $f_C$ = 1.0 MHz, VDD = 0V ( <b>Note 1</b> )		
		Operating Current	—	250	mA	VDD = 3.45V, FCLK = 10 MHz, SO = Open		
$\langle r \rangle$	loos	Standby Current (Sleep mode)	—	TBD	μA	$\overline{CS}$ = VDD, Inputs tied to VDD or VSS		

**Legend:** TBD = To Be Determined **Note 1:** This parameter is periodically sampled and not 100% tested.

#### TABLE 16-1: AC CHARACTERISTICS: ENC28J60 (INDUSTRIAL AND COMMERCIAL)

	Standard Operating Conditions
AC CHARACTERISTICS	$-40^{\circ}C \le TA \le +85^{\circ}C$ , $3.14V \le VDD \le 3.45V$ (Industrial)
	$0^{\circ}C \le TA \le +70^{\circ}C$ , $3.14V \le VDD \le 3.45V$ (Commercial)

#### TABLE 16-2: OSCILLATOR TIMING CHARACTERISTICS

Param. No.	Sym	Characteristic	Min	Мах	Units	Conditions
	Fosc	Clock In Frequency	25	25	MHz	$\bigcirc \bigcirc$
	Tosc	Clock In Period	40	40	ns	
	TDUTY	Duty Cycle (external clock input)	40	60	%	
	$\Delta f$	Clock Tolerance	—	±50	ppm	$\bigtriangledown$

Note: This parameter is periodically sampled and not 100% tested.

#### TABLE 16-3: RESET AC CHARACTERISTICS

Param. No.	Sym	Characteristic	Min	Max	Units	Conditions
	trl	RESET Pin High Time		$\geq$ –	μs	

#### TABLE 16-4: CLKOUT PIN AC CHARACTERISTICS

Param. No.	Sym	Characteristic	Min	Max	Units	Conditions
	t <sub>h</sub> CLKOUT	CLKOUT Pin High Time	TBD	—	ns	(Note 1)
	t <sub>I</sub> CLKOUT	CLKOUT Pin Low Time	TBD	_	ns	(Note 1)
	t <sub>r</sub> CLKOUT	CLKOUT Rin Rise Time	—	TBD	ns	Measured from 0.3 VDD to 0.7 VDD ( <b>Note 1</b> )
	t <sub>f</sub> CLKOUT	CLKOUT Pin Fall Time	—	TBD	ns	Measured from 0.7 VDD to 0.3 VDD (Note 1)
	t <sub>d</sub> CLKOUT	CLKOUT Propagation Delay		TBD	ns	

Legend: TBD = To Be Determined

Note 1: CLKQUT prescaler is set to divide by one. This parameter is periodically sampled and not 100% tested.

#### TABLE 16-5: REQUIREMENTS FOR EXTERNAL MAGNETICS

Parameter	Min	Norm	Max	Units	Conditions
RX Turns Ratio	_	1:1	—	—	
TX Turns Ratio		1:1	—		Transformer Center Tap = 3.3V
Insertion Loss	0.0	0.6	1.1	dB	
Primary Inductance	350	—	—	μH	8 mA bias
Transformer Isolation	—	1.5	—	kV	
Differential to Common Mode Rejection	40	—	—	dB	0.1 to 10 MHz
Return Loss	-16	—	—	dB	


#### TABLE 16-6: SPI™ INTERFACE AC CHARACTERISTICS


Param. No.	Sym	Characteristic	Min	Мах	Units	Conditions
	FCLK	Clock Frequency	DC	10	MHZ	$\sim$
1	Tcss	CS Setup Time	100	-<<	ns	$\sim$
2	Тсѕн	CS Hold Time	100		ns	
3	TCSD	CS Disable Time	100	((-))	ns	
4	Tsu	Data Setup Time	2 /		ns	
5	THD	Data Hold Time	10	7 –	ns	
6	TR	Clock Rise Time	$\mathcal{L}$	TBD	μs	(Note 1)
7	TF	Clock Fall Time	$\langle z \rangle$	TBD	μs	(Note 1)
8	Тні	Clock High Time	TBD	—	ns	
9	Tlo	Clock Low Time	TBD	_	ns	
10	Τv	Output Valid from Clock Low	_	TBD	ns	
11	TDIS	Output Disable Time	<u> </u>	TBD	ns	(Note 1)

Legend: TBD = To Be Determined

**Note 1:** This parameter is not 100% tested.







NOTES:


#### 17.0 PACKAGING INFORMATION

#### 17.1 **Package Marking Information**

#### 28-Lead SPDIP



#### 28-Lead SOIC



Standard PICmicro device marking consists of Microchip part number, year code, week code, and traceability code. For PICmicro device marking beyond this, certain price adders apply. Please check with your Microchip Sales Office. For QTP devices, any special marking adders are included in QTP price.




#### Example



#### 17.2 **Package Details**

The following sections give the technical details of the packages.

#### 28-Lead Skinny Plastic Dual In-line (SP) – 300 mil Body (PDIP)



	Units	INCHES*			MILLIMETERS		
Dimension	Limits	MIN	NOM	MAX	MIN	NOM	MAX
Number of Pins	n		28			28	
Pitch	р		.100			2.54	
Top to Seating Plane	Α	.140	.150	.160	3.56	3.81	4.06
Molded Package Thickness	A2	.125	.130	.135	3.18	3.30	3.43
Base to Seating Plane	A1	.015			0.38		
Shoulder to Shoulder Width	Е	.300	.310	.325	7.62	7.87	8.26
Molded Package Width	E1	.275	.285	.295	6.99	7.24	7.49
Overall Length	D	1.345	1.365	1.385	34.16	34.67	35.18
Tip to Seating Plane	L	.125	.130	.135	3.18	3.30	3.43
Lead Thickness	С	.008	.012	.015	0.20	0.29	0.38
Upper Lead Width	B1	.040	.053	.065	1.02	1.33	1.65
Lower Lead Width	В	.016	.019	.022	0.41	0.48	0.56
Overall Row Spacing §	eB	.320	.350	.430	8.13	8.89	10.92
Mold Draft Angle Top	α	5	10	15	5	10	15
Mold Draft Angle Bottom	β	5	10	15	5	10	15

\* Controlling Parameter

§ Significant Characteristic


Dimension D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed

.010" (0.254mm) per side. JEDEC Equivalent: MO-095

Drawing No. C04-070

Notes:

#### 28-Lead Plastic Small Outline (SO) – Wide, 300 mil Body (SOIC)



	Units	INCHES*			MILLIMETERS		
Dimension	Limits	MIN	NOM	MAX	MIN	NOM	MAX
Number of Pins	n		28			28	
Pitch	р		.050			1.27	
Overall Height	Α	.093	.099	.104	2.36	2.50	2.64
Molded Package Thickness	A2	.088	.091	.094	2.24	2.31	2.39
Standoff §	A1	.004	.008	.012	0.10	0.20	0.30
Overall Width	E	.394	.407	.420	10.01	10.34	10.67
Molded Package Width	E1	.288	.295	.299	7.32	7.49	7.59
Overall Length	D	.695	.704	.712	17.65	17.87	18.08
Chamfer Distance	h	.010	.020	.029	0.25	0.50	0.74
Foot Length	L	.016	.033	.050	0.41	0.84	1.27
Foot Angle Top	φ	0	4	8	0	4	8
Lead Thickness	С	.009	.011	.013	0.23	0.28	0.33
Lead Width	В	.014	.017	.020	0.36	0.42	0.51
Mold Draft Angle Top	α	0	12	15	0	12	15
Mold Draft Angle Bottom	β	0	12	15	0	12	15


\* Controlling Parameter § Significant Characteristic

Notes:

Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side.

JEDEC Equivalent: MS-013 Drawing No. C04-052

28-Lead Plastic Shrink Small Outline (SS) – 209 mil Body, 5.30 mm (SSOP)



	Units		INCHES			MILLIMETERS*		
Dimension Li	nits	MIN	NOM	MAX	MIN	NOM	MAX	
Number of Pins	n		28			28		
Pitch	р		.026			0.65		
Overall Height	A	-	-	.079	-	-	2.0	
Molded Package Thickness	A2	.065	.069	.073	1.65	1.75	1.85	
Standoff	A1	.002	-	-	0.05	-	-	
Overall Width	E	.295	.307	.323	7.49	7.80	8.20	
Molded Package Width	E1	.009	.209	.220	5.00	5.30	5.60	
Overall Length	D	.390	.402	.413	9.90	10.20	10.50	
Foot Length	L	.022	.030	.037	0.55	0.75	0.95	
Lead Thickness	с	.004	-	.010	0.09	-	0.25	
Foot Angle	f	0°	4°	8°	0°	4°	8°	
Lead Width	В	.009	-	.015	0.22	-	0.38	


\*Controlling Parameter

Notes:

Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side.

JEDEC Equivalent: MO-150

# 28-Lead Plastic Quad Flat No Lead Package (ML) 6x6 mm Body (QFN) – With 0.55 mm Contact Length (Saw Singulated)



	Units	INCHES			MILLIMETERS*		
Dimension Limi	ts	MIN	NOM	MAX	MIN	NOM	MAX
Number of Pins	n		28			28	
Pitch	е		.026 BSC			0.65 BSC	
Overall Height	А	.031	.035	.039	0.80	0.90	1.00
Standoff	A1	.000	.001	.002	0.00	0.02	0.05
Contact Thickness	A3		.008 REF		0.20 REF		
Overall Width	Е	.232	.236	.240	5.90	6.00	6.10
Exposed Pad Width	E2	.140	.146	.152	3.55	3.70	3.85
Overall Length	D	.232	.236	.240	5.90	6.00	6.10
Exposed Pad Length	D2	.140	.146	.152	3.55	3.70	3.85
Contact Width	b	.009	.011	.013	0.23	0.28	0.33
Contact Length	L	.020	.024	.028	0.50	0.60	0.70

\*Controlling Parameter Notes:

JEDEC equivalent: MO-220 Drawing No. C04-105

Revised 05-24-04

NOTES:

#### INDEX

В
Block Diagrams
Crystal Oscillator Operation5
ENC28J60 Architecture3
Ethernet Buffer Organization18
Ethernet Packet Format
External Clock Source5
External Connections7
I/O Level Shifting
3-State Buffers8
AND Gate8
Interrupt Logic65
LEDB Polarity Configuration8
Memory Organization11
On-Chip Reset Circuit59
Typical Interface4
Broadcast Filter
Built-in Self-Test Controller79
Address Fill Mode 80
Associated Registers81
EBSTCS registers 80
EBSTSD Register 80
Pattern Shift Fill Mode81
Random Data Fill Mode 80
Random Data Fill with Race Mode80
Use

## С

Checksum Calculations	
CLKOUT Pin	6
Control Register Map	
Control Register Summary	
Control Registers	

### D

DMA Controller	75
Access to Buffers	17
Associated Registers	76
Checksum Calculations	76
Copying Memory	75
Duplex-Mode	
Configuation and Negotiation	53

#### Е

Electrical Characteristics Absolute Maximum Ratings	
AC Characteristics	85
CLKOUT Pin AC	85
DC Characteristics	84
Oscillator Timing	85
Requirements for External Magnetics	86
Reset AC	85
SPI Interface AC	86
ENC28J60 Block Diagram	3
EREVID Register	22
Errata	2
Ethernet Buffer	17
Organization (Diagram)	18
Ethernet Overview	31
External Connections (Diagram)	7

### F

Filtering
Using AND Logic 50
Using OR Logic 49
Flow Control
Associated Registers 57
Full-Duplex Mode 55
Half-Duplex Mode55
Sample Full-Duplex Network (Diagram) 55
Full-Duplex-Mode
Operation
н
Half-Duplex-Mode
Operation
Hash Table Filter 52
I
I/O Level Shifting
Using 3-State Buffers 8
Using AND Gates 8
Initialization
MAC Settings 34
PHY Settings 38
Receive Buffer 33
Receive Filters
Transmit Buffer 33
Waiting for OST 33
Interrupts
DMA Flag (DMAIF)71
INT Enable (INTIE)66
Link Change Flag (LINKIF)71
Receive Error Flag (RXERIF) 70
Receive Packet Pending Flag (PKTIF)
Transmit Error Flag (TXERIF)
Transmit Interrupt Flag (TXIF)
WOL Interrupts71
L
LED Configuration
LEDB Polarity and Reset Configuration
LEDD Folanty and Reset Configuration
Μ
Magic Packet Filter 52
Magnetics and External Components7
Memory Organization 11
Multicast Filter
0
Oscillator
CLKOUT Transition
Crystal Oscillator
External Clock Source
Start-up Timer
•
P

Packaging Information	89
Details	90
Marking	89

Packet Format	
CRC Field	
Data Field	
Destination Address	
Padding Field	
Preamble/Start-of-Frame Delimiter	
Source Address	
Type/Length Field	
Pattern Match Filter	51
Per Packet Control Byte Format	
PHID Registers	
PHSTAT Registers	
PHY Register Summary	
PHY Registers	19
Reading	19
Scanning	19
Writing	19
Pinout Diagrams	1
Pinout I/O Descriptions	4
Power-Down	77
Associated Registers	77
Power-on Reset (POR)	60

#### R

Read Control Register (RCR)	
Reading and Writing to Buffers	17
Receive Buffer	17
Receive Filters	
Broadcast	52
Hash Table	52
Magic Packet	52
Multicast	
Pattern Match	51
Unicast	-
Using AND Logic	50
Using OR Logic	49
Receive Only Reset	60
Receiving Packets	43
Associated Registers	
Calculating Buffer Free Space	
Calculating Free Receive Buffer Space	
Calculating Random Access Address	44
Freeing Buffer Space	45
Reading	
Sample Packet Layout	43
Status Vectors	44
Registers	
EBSTCON (Self-Test Control)	
ECOCON (Clock Output Control)	
ECON1 (Ethernet Control 1)	
ECON2 (Ethernet Control 2)	
EFLOCON (Ethernet Flow Control)	
EIE (Ethernet Interrupt Enable)	
EIR (Ethernet Interrupt Request - Flag)	
ERXFCON (Receive Filter Control)	
ESTAT (Ethernet Status)	66
EWOLIE (Ethernet Wake-up on	
LAN Interrupt Enable)	72
EWOLIR (Ethernet Wake-up on	
LAN Interrupt Request - Flag)	73
MABBIPG (MAC Back-to-Back	
Inter-Packet Gap)	
MACON1 (MAC Control 1)	
MACON2 (MAC Control 2)	61

MACON3 (MAC Control 3)	35
MACON4 (MAC Control 4)	36
MAPHSUP (MAC-PHY Support)	62
MICON (MII Control)	
MISTAT (MII Status)	22
PHCON1 (PHY Control 1)	
PHCON2 (PHY Control 2)	
PHID (PHY Device ID)	
PHIE (PHY Interrupt Enable)	
PHIR (PHY Interrupt Request - Flag)	69
PHLCON (PHY Module LED Control)	9
PHSTAT1 (Physical Layer Status 1)	23
PHSTAT2 (Physical Layer Status 2)	24
Reset	59
MAC and PHY Subsystem Resets	61
Power-on Reset	60
Receive Only Reset	
System Reset	60
Transmit Only Reset	60

#### S

Serial Peripheral Interface. See SPI. SPI

0		
	Bit Field Clear Command	29
	Bit Field Set Command	29
	Instruction Set	26
	Overview	25
	Read Buffer Memory Command	28
	Read Control Register Command	27
	System Command	30
	Write Buffer Memory Command	29
	Write Control Register Command	28
SPI.	-	
Syst	em Reset	60

#### т

-	
Termination Requirement	7
Timing Diagrams	
CLKOUT Transition	6
Read Control Register Command	
Sequence (ETH)	27
Read Control Register Command	
Sequence (MAC/MII)	27
SPI Input	87
SPI Input Timing	25
SPI Output	87
SPI Output Timing	25
System Command Sequence	
Write Buffer Memory Command Sequence	
Write Control Register Command Sequence	
Transmit Buffer	17
Transmit Only Reset	60
Transmitting Packets	39
Associated Registers	42
Sample Packet Layout	
Status Vectors	
Typical ENC28J60-Based Interface	4
U	
Unicast Filter	51
W	

Wake-up on LAN (WOL)	71
WWW, On-Line Support	2

#### **ON-LINE SUPPORT**

Microchip provides on-line support on the Microchip World Wide Web site.

The web site is used by Microchip as a means to make files and information easily available to customers. To view the site, the user must have access to the Internet and a web browser, such as Netscape<sup>®</sup> or Microsoft<sup>®</sup> Internet Explorer. Files are also available for FTP download from our FTP site.

#### Connecting to the Microchip Internet Web Site

The Microchip web site is available at the following URL:

#### www.microchip.com

The file transfer site is available by using an FTP service to connect to:

#### ftp://ftp.microchip.com

The web site and file transfer site provide a variety of services. Users may download files for the latest Development Tools, Data Sheets, Application Notes, User's Guides, Articles and Sample Programs. A variety of Microchip specific business information is also available, including listings of Microchip sales offices, distributors and factory representatives. Other data available for consideration is:

- Latest Microchip Press Releases
- Technical Support Section with Frequently Asked Questions
- Design Tips
- Device Errata
- Job Postings
- Microchip Consultant Program Member Listing
- Links to other useful web sites related to Microchip Products
- Conferences for products, Development Systems, technical information and more
- · Listing of seminars and events

# SYSTEMS INFORMATION AND UPGRADE HOT LINE

The Systems Information and Upgrade Line provides system users a listing of the latest versions of all of Microchip's development systems software products. Plus, this line provides information on how customers can receive the most current upgrade kits. The Hot Line Numbers are:

1-800-755-2345 for U.S. and most of Canada, and

1-480-792-7302 for the rest of the world.

#### **READER RESPONSE**

It is our intention to provide you with the best documentation possible to ensure successful use of your Microchip product. If you wish to provide your comments on organization, clarity, subject matter, and ways in which our documentation can better serve you, please FAX your comments to the Technical Publications Manager at (480) 792-4150.

Please list the following information, and use this outline to provide us with your comments about this document.

To:	Technical Publications Manager	Total Pages Sent
RE:	Reader Response	
From	n: Name	
	Company	
		<u> </u>
	Telephone: ()	FAX: ()
Appl	ication (optional):	
Wou	ld you like a reply?YN	
Devi	ce: ENC28J60	Literature Number: DS39662A
Ques	stions:	
1. \	What are the best features of this do	cument?
_		
2. H	How does this document meet your	hardware and software development needs?
_		
_		
3. I	Do you find the organization of this o	locument easy to follow? If not, why?
_		
_		
4. \	What additions to the document do y	you think would enhance the structure and subject?
_		
_		
5. \	What deletions from the document c	ould be made without affecting the overall usefulness?
_		
_		
6. I	s there any incorrect or misleading i	nformation (what and where)?
_		
-		
7. H	How would you improve this docume	ent?
-		
-		

#### **PRODUCT IDENTIFICATION SYSTEM**

To order or obtain information, e.g., on pricing or delivery, refer to the factory or the listed sales office.

PART NO.	<u>-x /xx</u>	Examples:
Device	Temperature Package Range	<ul> <li>a) ENC28J60-I/SP: Industrial temperature, SPDIP package.</li> <li>b) ENC28J60-I/SO: Industrial temperature, SOIC package.</li> <li>c) ENC28J60T-I/SO: Tape and Reel, Industrial</li> </ul>
Device	ENC28J60: Ethernet Controller w/SPI™ Interface ENC28J60T: Ethernet Controller w/SPI™ Interface (Tape and Reel)	<ul> <li>c) ENC20001 #001 rape and reck, maddular temperature, SOIC package.</li> <li>d) ENC28J60-C/SS: Commercial temperature, SSOP package.</li> <li>e) ENC28J60T-C/SS: Tape and Reel, Comercial</li> </ul>
Temperature Range	<ul> <li>I = -40°C to +85°C (Industrial) (SPDIP, SOIC and QFN packages only)</li> <li>C = 0°C to +70°C (Commercial) (SSOP packages only)</li> </ul>	<ul> <li>temperature, SSOP package.</li> <li>f) ENC28J60-I/ML: Industrial temperature, QFN package.</li> </ul>
Package	SP = SPDIP (Skinny Plastic DIP) SO = SOIC (Plastic Small Outline) SS = SSOP (Plastic Shrink Small Outline) ML = QFN (Quad Flat No Lead)	



# WORLDWIDE SALES AND SERVICE

#### AMERICAS

Corporate Office 2355 West Chandler Blvd. Chandler, AZ 85224-6199 Tel: 480-792-7200 Fax: 480-792-7277 Technical Support: http://support.microchip.com Web Address: www.microchip.com

Atlanta Alpharetta, GA Tel: 770-640-0034 Fax: 770-640-0307

Boston Westford, MA Tel: 978-692-3848 Fax: 978-692-3821

**Chicago** Itasca, IL Tel: 630-285-0071 Fax: 630-285-0075

**Dallas** Addison, TX Tel: 972-818-7423 Fax: 972-818-2924

Detroit Farmington Hills, MI Tel: 248-538-2250 Fax: 248-538-2260

**Kokomo** Kokomo, IN Tel: 765-864-8360 Fax: 765-864-8387

Los Angeles Mission Viejo, CA Tel: 949-462-9523 Fax: 949-462-9608

**San Jose** Mountain View, CA Tel: 650-215-1444 Fax: 650-961-0286

Toronto Mississauga, Ontario, Canada Tel: 905-673-0699 Fax: 905-673-6509

#### ASIA/PACIFIC

Australia - Sydney Tel: 61-2-9868-6733 Fax: 61-2-9868-6755

**China - Beijing** Tel: 86-10-8528-2100 Fax: 86-10-8528-2104

**China - Chengdu** Tel: 86-28-8676-6200 Fax: 86-28-8676-6599

**China - Fuzhou** Tel: 86-591-8750-3506 Fax: 86-591-8750-3521

**China - Hong Kong SAR** Tel: 852-2401-1200 Fax: 852-2401-3431

China - Shanghai Tel: 86-21-5407-5533 Fax: 86-21-5407-5066 China - Shenyang Tel: 86-24-2334-2829 Fax: 86-24-2334-2393

**China - Shenzhen** Tel: 86-755-8203-2660 Fax: 86-755-8203-1760

**China - Shunde** Tel: 86-757-2839-5507 Fax: 86-757-2839-5571

**China - Qingdao** Tel: 86-532-502-7355 Fax: 86-532-502-7205 ASIA/PACIFIC

India - Bangalore Tel: 91-80-2229-0061 Fax: 91-80-2229-0062

**India - New Delhi** Tel: 91-11-5160-8631 Fax: 91-11-5160-8632

**Japan - Kanagawa** Tel: 81-45-471- 6166 Fax: 81-45-471-6122

Korea - Seoul Tel: 82-2-554-7200 Fax: 82-2-558-5932 or 82-2-558-5934

**Singapore** Tel: 65-6334-8870 Fax: 65-6334-8850

**Taiwan - Kaohsiung** Tel: 886-7-536-4818

Fax: 886-7-536-4803 Taiwan - Taipei Tel: 886-2-2500-6610 Fax: 886-2-2508-0102

**Taiwan - Hsinchu** Tel: 886-3-572-9526 Fax: 886-3-572-6459

#### EUROPE

Austria - Weis Tel: 43-7242-2244-399 Fax: 43-7242-2244-393

**Denmark - Ballerup** Tel: 45-4450-2828 Fax: 45-4485-2829

France - Massy Tel: 33-1-69-53-63-20 Fax: 33-1-69-30-90-79

**Germany - Ismaning** Tel: 49-89-627-144-0 Fax: 49-89-627-144-44

**Italy - Milan** Tel: 39-0331-742611 Fax: 39-0331-466781

**Netherlands - Drunen** Tel: 31-416-690399 Fax: 31-416-690340

England - Berkshire Tel: 44-118-921-5869 Fax: 44-118-921-5820

10/20/04